

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bk Bldg, Wichita, Kansas.


ROXANE PETROLEUM CORP.
Nevitt No. 1.

SEC. 14 T. 32 R. 2E.
Tract 3 NE $\frac{1}{4}$
30' WL Tract 3 195' S. CL Cedar
Street.

DEEPENING RECORD.

County. Sumner.

Total Depth. 4000
Comm. 7-2-27 Comp. 8-30-27
Shot or Treated.
Contractor.
Issued. 4-17-37.
Casing.



20" 300'
15 $\frac{1}{2}$ " 520'
12 $\frac{1}{2}$ " 1252'

Elevation. 1170

Production. 374 B.

Figures Indicate Bottom of Formations.

soil	10	lime	925	shzle	1996
sand	15	slate blue	935	lime	1998
gravel HFW	20	sdv lime 6BW	945	sand and shale	2005
shale	25	lime	955	2005 equals 1992 SLC	
lime	55	shale blue	985	s and brown soft	1997
slate	85	lime	990	show oil 1992	
shale blue	115	shale blue	1050	sand brown soft	2002
lime	120	lime	1055	Free oil in hole.	
shale blue	125	shale blue	1090	sand grey shale break	2007
red rock	130	lime	1140	sand brown shale break	2012
shale blue	160	sdv lime	1145	50' oil in hole.	
sdv lime	175	sdv lime	1150	sand lighter	2016
shale blue	185	shale blue	1165	sand light soft	2019
lime	195	shale	1170	sand dark soft	2024
sdv lime 7 BW	210	lime	1174	2024 equals 2031 SLC	
lime	215	shale white	1187	Bailed hole dry 1BW 6BO	
sand HFW	220	lime	1192	sand some shale	2032
lime	226	red rock	1198	no increase in oil	
shale blue	233 $\frac{1}{2}$	sand	1205	sand and shale no inc	2036
lime	300	shale blue	1223	sand grey	2039
shale blue	306	lime	1226	sand grey	2046
lime	310	shale blue 15BWPH	1250	2046 equals 2049 SLC	
shale blue	325	lime	1252	sdv shale probable inc	
lime	335	1252 equals 1240 SLC		water	2051
red rock	340	lime	1241	sdv shale	2053
broken lime	375	shale	1270	shale blue	2055
4 BW 350' 6 BW 370'		lime	1283	shale sdv	2058
lime	400	show oil 1283-85		sdv lime coarse	2062
red rock	410	sand	1290	sdv lime	2066
lime	475	show oil & 6 BWPH		sand fine white	2067
sdv lime	480	sdv lime	1293	sand fine white	2072
slate blue	485	shale grey	1215	sand coarse dark	2075
lime	495	sdv lime	1320	sand	2078
shale blue	510	lime	1325	2078 equals 2080 SLC	
sdv lime HFW 510	515	shale	1370	hole filled up with oil	
lime	535	carrying 6 BW		sand	2089
red rock	545	shale white	1390	Total Depth.	
shale blue	570	lime 6BWPH	1394		
lime	575	lime	1400	DEEPENING RECORD.	
shale blue	580	slate 6 BWPHR	1405	SHELL PETROLEUM.	
lime	610	lime	1460	Comm. 12-4-35	
shale blue	670	lime 6 BWPHR	1508	Comp. 2-26-36.	
sdv lime 2 BW	680	shale blk 8 BWPHR	1510	Prod. 20 bbls oil 700 B.W.	
shale blue	690	lime	1535	Pumped in 24 hours.	
lime	720	shale	1545	Casing - 16" 570'	
shale blue	730	lime carrying 8BWPH	1583	13" 1214'	
lime	745	shale	1585	7" 2888'	
shale blue	750	lime	1635	sand 2092-	2105
lime	760	shale blue	1645	sand and shale	2115
shale blue	790	shale	1680	shale and lime	2150
sdv lime 6 BW	805	sand	1695	shale and shells	2410
slate blue	810	5 BWPHR 1693-95		shale	2420
lime	815	sdv shale	1705	lime and shale	2431
slate	820	HFW 1700'		lime brown	2432 $\frac{1}{2}$
shale blue	870	sand	1710	lime brown with shale blk	
lime	890	shale	1805	breaks	2442 $\frac{1}{2}$
red rock	895	shale white	1825	shale blk	2447
shale blue	905	sand show oil	1827	lime brown	2449
lime	910	shale white	1890	lime	2497
shale blue	915	slate white	1985	OVER	

Shell Petro.

14-32-2E. Nevitt No. 1.

lime and shale	2614
lime	2670
shale and shells	2691
shale and lime	2840
shale and shells	2870
shale	2879
sdv lime	2885
lime	2887
dolomite	2902
300' oil in hole at 2913	
600' oil in hole 2 hours while drilling	
2913-2914	
Swabbed 120 bbls oil and no water	
1400' oil in hole 2930	
dolomite	2964
Total Depth.	
Plugged back to dolomite	2951

SHELL PETRO.

SHEET DRILLING.

Comm. 1-22-37 Comp. 5-25-37

Prod. Salt Wtr Disposal.

5 1/2 casing 3035

L.B. to 2944.

drilled out cement	2950
drilling out cement and	
lead plug	2966
dolomite light grey hd some	
chert	2980
lime	3003
lime sdv	3022
lime	3032
lime hard grey	3170
lime hard wh	3366
lime sdv hard	3385
lime	3408
lime sdv	3418
lime hard grey	3427

lime sdv	3452
lime	3470
lime hard brown	3485
lime	3579
lime sdv	3591
lime hard grey	3604
lime	3651
lime sdv	3662
lime	3799
S.L.C. 3799 equals	3808
lime	3818
lime sdv	3828
lime sdv grey	3848
lime	3858
lime sdv	3878
lime	3939
sand grey red and blue	3951
sand red	3968
granite hard red	3993
granite	4000
Total Depth.	