

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location 504' E CL Midland Valley R. R., 36' S of SL
Cedar Street, Tract # 3.

Casing Record Sec 14 T 32 R 2 E.

10" 1303 Farm Nevitt No. 3 County Sumner


20" 62 8 1/4" 1712 Company Roxane Petroleum Corp.

15 1/2" 390 65/8" 2008 Contractor

12 3/8" 730 53/16" Commenced 12-20-27. Completed 1-22-28.

Total Depth 2101'. Shot Quarts Between

Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production 323 bbls.

Date Issued. 2/4/28.

Formation	Depth	Formation	Depth
soil	10	shale 12 BWP at 925'	987
shale	30	lime	992
sand	40	shale	1045
shale	48	lime	1050
sandy lime	70	blue shale	1060
red rock	84	shale	1065
shale	90	lime	1070
sand 4 BW	95	shale	1075
shale	98	lime	1120
sand	125	shale	1158
shale	155	lime	1175
sandy lime	170	shale	1190
shale	175	red rock	1195
lime	178	lime	1225
shale	190	shale	1280
lime 15 BW at 250'	300	lime	1288
shale 25 BW at 270'	320	sand HFW	1300
lime	330	lime	1315
red rock	340	shale	1330
sandy lime	357	lime	1350
blue slate	360	shale	1385
sandy lime	390	lime	1390
red rock	400	shale	1405
lime	410	lime	1465
shale	455	shale black	1470
sand HFW at 460'	465	lime	1515
shale	480	shale	1525
lime	485	lime	1585
shale	510	shale	1655
sand	525	sand HFW 1655-85'	1675
shale	530	shale	1720
red rock	545	sandy lime	1807
shale	590	shale	1840
lime	600	lime	1850
shale	655	shale	2005
lime	665	sand & shale	2006
sandy lime	680	S. L. C.	2006-2008'
blue shale	695	1st show oil 2018-23'	
blue slate	717	sand & shale	2023
shale	730	sand some shale	2038
lime	732	1/4 blr free oil	
blue shale	745	sand & shale	2045
lime	750	sand	2093
shale	755	sand SLM at 2101'	2101
lime	757	Some Gas	
shale	885		
lime 1 BW PH	890	Total Depth	2101'
shale	923		
sand	940		