

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 Union National Bank Bldg, Wichita, Kansas.

SHELL PETROLEUM CORP.
 Z. W. Nevitt No. 4

SEC. 14 T. 32 R. 2E.
 CEL SW NE
 234' E CL MV RR & 185' N CL
 Santa Fe RR

Total Depth, 2969
 Form. 10-8-35 Comp. 11-17-35.
 Salt or Treated, 3000 Gal.
 Contractor, Olson Drilling Co.
 Issued, 12-21-35

County, Sumner.



CASING.

16" 233'
 85/8" 2020'

Elevation.

Production Pot. 565 B.

Figures Indicate Bottom of Formations.

	103	lime	2442
sand hard	144	sand	2458
rock	185	shale	2462
rock and sand	199	lime	2515
rock	233	lime	2541
lime hard	300	broken lime and shale	2549
lime hard	320	lime	2574
shale	340	lime and shale	2600
broken lime	462	shale and lime shells	2621
shale & broken lime	485	sdv lime	2626
lime	505	lime and shale	2654
shale and shells	525	shale and lime shells	2692
sdv lime	560	shale	2713
red bed and shale	579	lime	2736
shale and lime shells	595	broken shale and lime	2766
shale	675	shale and broken lime	2818
sdv lime	750	broken lime and shale	2875
broken lime	800	shale blk with lime streaks	2881
shale	810	shale grey	2884
shale and lime shells	945	shale grey green	2890
sdv shale	970	2890 equals 2889 S.L.C.	
shale	1019	sdv shale grey	2894
broken lime & shale	1084	shale green	2896
shale and lime shells	1110	shale blk with lime streaks	2903
lime brown	1215	shale dull green	2918
shale and broken lime	1220	shale brown sporiferous	2920
shale blue	1276	sand with green shale	2925
sdv shale and lime	1302	showing oil	
lime	1315	sdv green shale	2930
shale	1338	sand with green shale	2931½
lime	1345	showing oil	
shale	1380	shale green with dolomite streaks	
shale and shells	1395	showing oil	2932½
lime brown	1405	shale green with sand streaks	2938½
shale and broken lime	1441	shale green with sand streaks	2946
brown lime and shale	1465	shale with sand streaks	2953
shale	1497	sand tight	2955
broken lime and shale	1540	dolomite	2958
lime	1560	2958 SIM.	
lime and shale	1570	dolomite	2966
sand and lime	1595	600' OIH in 6 hours	2862
sdv shale and lime	1709	swabbed and bailed 142½ bbls oil and	
shale and lime shells	1730	19 bbls water in 15 hours	2966
lime brown	1760	dolomite cherty	2969
shale	1785	fluid level inc. from 200' to 2000'	
lime	1863	in 3½ hours while drilling	2966-2969
shale and lime shells	1880	Total Depth	
shale	1890		
lime	1920		
sdv shale and lime	1989		
shale	1997		
shale and brown lime	2111		
sand	2114		
shale	2130		
broken lime and shale	2141		
sand	2157		
lime	2330		
shale	2429		
shale and shells	2436		
shale			