


WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION Out Lot 22 in the City of Oxford SEC 14 T 32 R 2 E.

20" 10" FARM Scroggin NO. 1 COUNTY Sumner
 15 1-2 8 1-4 COMPANY Jarvis & Shawver
 12 1-2 6 5-8 CONTRACTOR
 5 3-16 COMMENCED 10-25-27. COMPLETED 11-15-27.
 TOTAL DEPTH 2088 $\frac{1}{2}$ ' SHOT 30 QUARTS BETWEEN 2068-2088'
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO



FIGURES INDICATE BOTTOM OF FORMATIONS.
 REMARKS 12/24/27.

ELEVATION
 INITIAL PRODUCTION 700 bbls.
 (Scout ticket)

Formation	Depth	Formation	Depth
sand	14	water sand	1300
shale	20	lime	1360
lime	25	shale break	1400
shale	30	lime	1415
lime	35	shale	1450
shale	50	lime	1500
sand Water	60	sand lime	1510
lime Set 20" pipe at 60'	75	lime	1550
lime	100	shale	1560
shale	120	lime	1580
lime	130	shale	1620
lime	150	lime	1640
shale	170	sand HFW 1645'	1645
lime	180	shale	1700
shale	190	slate	1750
lime	215	lime	1765
lime	235	white shale	1775
lime	255	Show of oil & 2 BW at 1775'	
lime	275	sand	1790
lime	295	lime	1800
shale	305	shale	1820
red rock	310	slate black	1967
Set 15 $\frac{1}{2}$ " pipe at 310'		lime sandy	1982
lime	335	sand	2088 $\frac{1}{2}$ '
lime	350		
shale	360	Total Depth	2088 $\frac{1}{2}$ '
shale	380		
red rock	390		
shale	400		
shale	415		
lime	420		
shale	425		
lime	447		
Pulled 15 $\frac{1}{2}$ " pipe to straight			
ream. Straight reamed from			
310 to 447' & run back 15 $\frac{1}{2}$ "			
pipe.			
lime	470		
lime	535		
red rock	545		
lime	615		
lime Water 8 blrs. at	695		
lime 690'	755		
shale	775		
lime	780		
shale	805		
lime	825		
sandy shale 4 BW 840'	850		
lime	875		
shale	925		
sand HFW at 925'	940		
lime	947		
Set 12 $\frac{3}{4}$ " pipe at 947'			
shale	1025		
lime	1050		
slate & lime	1095		
lime	1110		
shale	1150		
lime hard	1180		
shale	1220		
lime	1230		
shale	1260		
lime	1285		