

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bk Bldg, Wichita, Kansas.,

STANLEY ET AL.
Scroggin No. 1.

DEEPENING RECORD.

SEC. 14 T. 32 R. 2E.
NE¹/₄ Blk 53
204'E of CL MVRR 17' S CL
Cedar Street.
County, Sumner.

Total Depth. 2952 P.B. 2948'
Comm. 8-31-27 Comp. 10-19-27
Shot or Treated.
Contractor.
Issued. 3-21-36
CASING.



20" 15' 8¹/₄" 1750'
15¹/₂" 123 7" 1994' UR 2260
12¹/₂" 570' 5¹/₂" 2873'
10" 1000'

Elevation.

Production. 744 B.

Figures Indicate Bottom of Formations.

surface dark soft	15	lime grey hard	1186	lime	2440
lime soft light	50	shale blue soft	1196	shale	2444
water sand light sft	75	lime grey hard	1205	lime	2517
fresh water		shale pink soft	1215	lime	2545
lime light hard	80	sdv lime light soft	1235	sdv shale	2555
mud blue light sft	85	good sh oil 1250		slate	2565
lime light hard	123	lime light hard	1250	lime	2568
shale blue soft	130	shale light soft	1295	3 BWPHR 2545-2555	
red rock red soft	140	lime grey hard	1340	lime Rainbow sh oil	2624
brkn lime light sft	200	oil and water 1305		shale 2588-95	2640
water sand light sft	225	lime shells slate darksft	1365	lime	2645
lime light soft	285	shale light soft	1405	shale	2654
lime light soft	300	lime light hard	1435	lime	2668
mud light soft	335	broken lime light sft	1437	shale	2680
lime soft	340	lime white hard	1465	shale	2680
mud red soft	345	broken lime light soft	1500	broken lime	2685
lime hard white	385	lime light hard	1540	shale	2714
lime hard grey	395	shale dark	1555	shale	2734
mud red soft	405	lime	1650	lime	2742
shale blk soft	445	shale blue	1695	shale and shells	2760
lime light hard	450	lime	1700	lime	2780
sdv shale light soft	460	sdv shale	1740	lime	2800
shale light soft	480	water sand	1755	shale	2805
shale dark soft	500	shale blue	1760	lime	2815
lime grey hard	503	sdv shale	1785	shale	2830
shale blue soft	515	shale blue	1850	sdv shale	2835
lime light soft	530	lime hard	1860	2835 equals 2826 SLC	
shale light soft	550	shale	1972	shale and shells	2850
red rock soft	560	lime	1976	sdv shale	2870
shale blue soft	570	shale	1985	dolomite	2882
shale light soft	575	sand	1994	show oil 2878	
shale red soft	585	show oil 1996		show oil 2882	
lime light soft	605	show oil 2005		sand	2884
shale blue soft	611	more oil 2011		shale & shells	2929
lime grey hard	626	more oil 2018		sand and shale	2932
shale blk soft	629	sdv shale	2026 ¹ / ₂	oil 2939-2942	
lime grey hard	637	sdv shale more oil wash	2035 ¹ / ₂	Swabbed 122 ¹ / ₂ B. in 12 H.	
shale blk very soft	650	Top hard sand more oil good		2935 equals 2942 SLC	
lime light soft	700	pay	2043	dolomite	2943
4 BW sdv lime light	715	more good pay and sand sft	2054	dolomite	2956
lime grey hard	732	1st gas sand extra soft	2063	Total Depth.	
shale blue soft	735	sand light real pay	2072	Plugged back to dolomite	
lime light hard	750	sand light real pau	2076		2948
shale blk soft	752	sand light real pay	2080		
lime grey hard	758	sand light real pay	2085		
shale dark soft	770	sand darker more coarse	2088		
shale dark soft	790	sand changed to light	2090 ¹ / ₂		
shale dark soft	820	sand light	2094 ¹ / ₂		
lime grey hard	845	Cable Meas. 2090 bottom of			
shale blue soft	888	hole. 2089 foot caving.			
lime grey hard	910	Total Depth.			
shale blue soft	1000	<u>DEEPENING RECORD.</u>			
shale blue soft	1080	STANLEY & JARVIS-SHELL.			
lime light hard	1090	Comm. 9-4-35 Comp. 2-10-36.			
shale dark soft	1106	Prod. Pot. 373 B. O. 400 BW			
show oil		24 hour pumping.			
sdv lime grey hard	1111	sand 2090-	2172		
shale dark soft	1113	shale	2178		
lime grey hard	1140	shale	2430		
shale light soft	1164	lime	2435		