

COMPANY **H. J. Parker.**SEC. **4** T. **31** R. **21E.**FARM **Woods**NO. **1**LOC. **NW SW DW****4-31-2E** ✓

TOTAL DEPTH


COMM. **2-6-1917**

COMP.

SHOT OR TREATED

CONTRACTOR

ISSUED

COUNTY **LaSalle.**

CASING

20 IN.	10 IN.
15 1-2	5 1-4
12 1-2	6 5-8
13 3-8	5 3-16

ELEVATION

PRODUCTION

DRY.

FIGURES INDICATE BOTTOM OF FORMATION

soil	10
gravel	22
quick sand	26
shale blue	57
lime brown	60
shale blk and shells	86
lime grey	100
shale	
black rock	106
lime grey soft	108
shale light	150
lime and shale	152
shale light and shells	204
lime grey	279
shale light	353
shale blue	358
no log	373
lime and shells	380
shale blk	386
lime and shells	387
shale light	420
shale dark	437
shale light	453
shale blk	465
sand	475
shale dark	486
sand	492 show of oil
shale blk	525
shale light	530
shale brown	545
shale blk	560
lime and flint	568
Total Depth.	

Pipe reported to be left in hole. Plugged.
Still makes a little gas in 1934. Producing
horizon not mentioned in log but most likely
is the chert.