

P. E. F.
Carl M. F.
out


J.A. HULL COMPANY.
Wallace No. 8

SEC. 24 T. 32 R. 4E.
CWL NW NW SE

DEEPENING RECORD.

Total Depth. 2433
Comm. 12-14-24 Comp. 1-23-25
Shot or Treated.
Contractor.,
Issued. 9-3-38

County Cowley.



CASING.

SEP 3 1938

12 1/2" 387'
10" 1127'
8 1/4" 1650'
65/8" 2150'
53/16" 222'11"

Elevation.

Production. 100 B.

Figures Indicate Bottom of Formations.

rod rock soft	210	lime wtr 1310	1350
shale	230	red rock	1355
lime	260	lime	1427
shale	270	shale	1435
lime	300	lime	1440
slate	315	sand	1455
lime	325	5 BW 1525-35	
slate	340	shale	1500
lime	355	show oil 1440-55	
shale	360	sand	1510
rod rock	390	lime	1515
lime	400	sand water 5 B.	1535
shale light	497	slate	1620
lime	545	lime	1636
shale	555	shale hole caving.	1650
lime	565	shale blue	1665
shale	602	red rock	1675
slate	625	shale	1685
lime	630	lime	1710
slate Gas 660	660	sdv shale	1750
lime hard	690	lime	1758
shale	700	slate white	1770
lime	705	lime	1790
slate	720	shale	1820
lime	735	slate	1905
shale	850	lime	1910
lime	860	sand HFW 1920	1945
shale	897	lime	1975
lime	910	sand	1985
slate	915	slate light	2000
lime	925	sdv lime	2020
sand	944	shale blue	2110
water 15 PER		sand	2145
slate	964	lime	2154
lime hole caving.	969	shale	2332
slate	1005	sand Oil	2335
lime	1010	Pay sand Oil	2348
rod rock	1015	Dry sand	2358
lime	1024	lime gray	2364
slate	1040	Total Depth.	
sand cave	1045		
slate blue	1070	DEEPENING RECORD.	
lime hard	1073	SINCLAIR PRAIRIE.	
slate	1092	Comm. -1-4-37	
lime	1100	Comp. 2-17-37	
slate	1105	Prod. - Salt water disposal.	
sand	1110	sand 2364-	2373
shale	1115	lime	2380
sand	1120	lime sdv	2390
lime	1127	sand	2431
shale	1206	shale sdv	2433
slate	1225	Total Depth.	
lime	1275		
shale	1302		