

G

Company: Eagle-Picher

Sec. 22 T. 32 R. 25

Farm: Hazel McFerron No. 3

Loc. NEc SE NE

Comm. March 23, 1943

County: Cherokee

Comp. April 1, 1943

Total Depth: 272

Contractor: Bill Swalley

Water Level: 200'

Driller: Archie Goforth

Elevation: 861

## Formation

	Thickness	Depth
soil and clay	15	15
shale, blue; sandstone	10	25
shale, blue	20	45
flint, light and dark gray	15	60
flint, gray and dark; some lime, gray	20	80
flint, gray and dark; jasperoid, gray	20	100
flint, light and dark gray	10	110
flint, light and dark gray; lime, gray	25	135
flint, speckled, light gray and pale brown; lime, brown	10	145
lime, brown; flint, light gray	50	195
flint, light gray soft	10	205
flint, light gray; jasperoid, brown	15	220
flint, light gray and pale brown; jasperoid, brown	5	225
flint, light gray and pale brown	5	230
flint, dark gray, pale brown and light gray; thin trace of zinc; specks of lead	5	235
flint, dark gray, pale brown and light gray; thin trace of zinc	2 $\frac{1}{2}$	237 $\frac{1}{2}$
flint, gray and dark gray; specks of zinc	2 $\frac{1}{3}$	240
flint, gray and dove gray; jasperoid, brown; thin trace of zinc	5	245
flint, light and dove gray; jasperoid, brown; specks of zinc	5	250
flint, gray and dark gray; jasperoid, brown; specks of zinc	5	255
flint, gray and dark gray; lime, gray	17	272