

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


6-32-3E

Company- H & M DRILLING
Farm- Chevront No. 1

SEC. 6 T. 32 R.3E
NE NE NW

Total Depth. 3389'
Comm. 12-13-60 Comp. 12-27-60
Shot or Treated.
Contractor.
Issued. 2-11-61

County Cowley
KANSAS



CASING:
8 5/8" 160' cem w/150 sx.

Elevation. 1167' RB

Production. Dry

Figures Indicate Bottom of Formations.

lime	204
lime & shale	265
shale & lime	330
lime w/shale	535
shale & lime	840
shale & lime	950
shale w/lime	1230
shale & lime	1745
shale w/lime	1762
shale & lime	2126
Stalnaker	2130
sand & shale	2234
shale	2511
K.C. lime	2725
lime & shale	2785
sand & shale	2805
lime	2864
lime & shale Oswego	2930
lime & shale	3005
shale	3069
Mississippi lime	3223
Miss. lime & shale	3292
Kinderhook shale	3329
Simpson	3336
Arbuckle lime	3389 RTD
Total Depth	

TOPS: SCOUT	
Iatan	2116
Stalnaker	2124
Kansas City	2514
Cleveland	2783
Cherokee	2940
Mississippi	3059
Kinderhook	3255
Simpson	3330
Arbuckle	3336