

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

PLOTTED
G. E. Jameson
card made out

DEEP ROCK OIL CORP.
C.C. Granston No. 3.

SEC. 30 T. 32 R. 6E
NW SW NE
1610' fr NL 330' fr WL

20-32-6E

Total Depth. 3510'
Comm. 12-10-37 Comp. 1-24-38
Shot or Treated.
Contractor.
Issued. 6-11-38

County. Cowley

CASING:
13" 85'
7" 3438'

JUN 11 1938



Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

clay	20	sand	1895	lime	3425
ohat	80	shale	2000	lime & shale	3437
lime rock	125	lime	2065	coring 3 1/2' recovery	3447
shale sholls, red bed	145	shale	2185	2' shale 1 1/2' chert	
lime lgt shale strks	220	shale & sholls	2190	show oil	
sdv lime white	235	shale	2195	Top Siliceous	3438
lime	255	coring 10' shale	2195-2205	drill pipe tally	3447
red bed	280	coring shale few strks		SLM	3445
shale blue & lime	340	lime	2215	Siliceous lime	3438-3510
lime sdv white	375	coring 100% recovery #3	2215-23	Total Depth.	
shale blue sticky	385	coring 100% recovery #4	2223-25		
lime grey & white	405	reaming	2225-35		
shale & sholls	435	coring sdv lime strks of		Note: When plug was	
shale	440	shale	2247	drilled hole filled up	
sdv lime & shale	500	finish cutting core #5	2247-52	approximately 300' with	
lime & sand hrd	510	coring 13' 6" recovery	2252-67	water. No oil.	
shale & lime sholls	610	sand	2299	Water bailed down easily	
lime & shale	635	sdv shale	2352	but filled up gradually	
shale & sholls	650	shale sticky	2385	to 3100' from bottom as	
lime & sdv shale	690	shale	2405	well was deepened.	
sdv shale	740	sdv shale	2419		
sdv lime	760	sdv lime	2430		
lime grey, wh hrd	800	lime & shale	2440		
lime & shale	850	shale & sholls	2479		
shale sticky	870	shale	2485		
lime & shale	895	lime	2505		
shale & sholls	905	lime & shale	2555		
lime & shale	925	sticky shale	2600		
shale & lime sholls	1055	shale & lime sholls	2610		
shale & sholls	1085	lime white	2620		
shale sticky	1100	lime brkn	2625		
lime & shale	1110	shale	2690		
lime	1135	lime & shale	2725		
lime & shale	1155	lime sholls & shale	2800		
shale hrd lime & sholls	1195	shale	2826		
sticky shale & sholls	1220	coring	2844		
shale sticky	1245	coring - 11' sdv shale	2853		
shale & lime	1280	coring 3' drk lime &			
sand	1305	strks of shale	2865		
green blue shale lime &		shale blue	2885		
sholls	1315	sdv shale & lime sholls	2970		
sdv lime	1320	shale & sholls	2994		
sdv lime & shale	1345	no log	2994-3005		
shale	1360	lime wh cherty	3030		
shale & sholls	1395	lime	3042		
shale red & blue	1435	lime blk	3055		
shale & sholls	1440	brkn lime	3080		
lime drk	1485	lime & sdv shale	3110		
shale & sholls	1610	lime	3120		
sdv lime	1620	sdv lime	3175		
shale & hrd sholls	1640	lime	3270		
lime sholls & shale	1650	running on iron dropped			
shale & sholls	1725	in hole	3279		
shale & lime sholls	1765	lime	3330		
shale sticky	1785	lime blk	3350		
shale & lime sholls	1810	lime	3400		
shale & sholls	1870	shale	3410		