

MURTA & WILSON-BESS & GRALAPP
Jennie Bell Turner No. 1.

SEC. 30 T. 32 R. 6E
NEC NW

30-32-6E

Total Depth. 2247'
Comm. 4-29-37 Comp. 5-28-37
Shot or Treated. 90 Qts. 2225-45
Contractor. Bess & Gralapp
Issued. 6-19-37

County. Cowley



CASING:

15 1/2" 381'
12 1/2" 1130'
10" 1432' UR 1680'
8 1/4" 1947'

JUN 19 1937

Elevation.

Production. Est 502 B.

Figures Indicate Bottom of Formations.

cellar & red rock	22	lime sdy	1025	lime	2060
shale	55	4 BWPB 1015-25		shale	2220
lime	62	shale	1100	sdv lime	2232
shale	85	lime	1135	sand	2247
red rock	90	s hale	1155	Total Depth.	
lime	135	lime	1190		
red rock	140	shale	1195	First oil at 2232	
lime	160	lime	1200		
shale	165	shale	1205		
lime	205	red rock	1210		
slate white	210	lime	1235		
red rock	215	shale	1243		
shale	225	lime	1275		
lime	235	shale	1285		
shale	250	sand	1310		
lime	275	HFW 1285-1300			
red rock	305	shale	1364		
lime	310	NOTE at 1360 Cable Meas.			
slate brown	320	the steel line measurement			
lime	325	was 1340, bottom of shale			
shale	340	is 1364			
lime	350	lime sdy	1372		
shale	365	shale	1377		
red rock	375	red rock	1381		
lime	400	shale	1385		
shale	446	sand	1395		
lime	465	shale	1404		
shale blue	475	sand	1416		
lime	485	lime	1422		
shale white	525	shale	1430		
lime	530	lime	1434		
shale	555	shale	1455		
lime	560	lime brkn	1480		
shale & shells	605	shale	1495		
shale	650	lime	1505		
lime	655	shale cave	1530		
shale	685	red rock	1555		
lime	700	lime sdy	1570		
shale & shells	780	shale white cave	1575		
lime	790	lime hole caving	1590		
shale	810	shale	1595		
lime	825	red rock	1630		
shale	830	shale blue	1680		
lime	845	lime	1693		
shale	850	shale	1730		
lime sdy	870	lime sdy	1745		
shale	910	shale	1820		
lime	915	lime	1828		
shale	940	shale	1861		
lime	945	sand	1888		
shale & shells	960	shale	1893		
lime	965	sand	1955		
shale	985	HFW 1893-1900			
lime	992	shale sdy	1962		
s hale	995	shale drk	1995		
lime	1015	lime	2022		