

32-32-7E  
NW NE

Elev. 1349' KB  
P. 110BOPD + 1 1/2" with  
Back

ROTARY DRILLING LOG

OWNER: Gralapp and Everly  
Nine-O-One Building  
Winfield, Kansas 67156

LEASE: Branson #1

LOCATION: NE NW NE 32-32S-7E  
Cowley, County, Kansas

CONTRACTOR: Watson Drilling Co., Inc.  
Nine-O-One Building  
Winfield, Kansas 67156


CASING: Ran 214 ft. of 3 3/4"  
casing. Cemented at  
207 ft. with 145 sacks  
HA-5.

Commenced: 8/28/69  
Completed: 9/5/69

Branson No. 1

Log Log

	0	45	shale and lime
	45	209	lime shale
	209	360	shale and lime
Iatan	360	720	shale shells
	720	970	shale and lime
Stalnaker	970	1260	shale and lime
	1260	1510	shale lime
Lansing	1510	1660	shale and sand
Hog	1660	1677	lime (Iatan)
Sayton	1677	1740	shale and sand
	1740	1920	shale and sand
Kansas City	1920	2115	shale lime stks.
Marmaton	2115	2235	shale and sand
Cherokee	2235	2340	sand and shale
Cattlemans Bn	2340	2470	lime shale
	2470	2610	lime and shale
Barthelmie Sd.	2610	2700	lime and shale
B. "	2700	2820	shale sand
	2820	2825	shale
	2825	2847	Core #1
		2847	T. D.



Core 2825-47

Ran 2855 ft. 5 1/2" casing,  
cemented with 75 sacks of  
salt saturated peamix at 2824 ft.

32-32-7E