

UNION NATIONAL BANK BLDG WICHITA KANSAS.

Location SW NE NE

Sec. 19 T. 32 R. 8E.


1056' fr NL & 1056' fr EL NE/4

Casing Record

County- Cowley.

10" 1202 Farm- Adams No. 1
 20" 8 1/2" 1498 Company- Roth & Faurot Oil & Gas Co.
 15" 65/8" 2217 Contr.-
 12" 925 53/16" Comm.- 3/21/30 Comp.- 8/22/30.

Total Depth 3042' Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.
 Date Issued. 12/13/1930

Elevation
 Initial Production
 1 M. Gas.

Formation	Depth	Formation	Depth	Formation	Depth
soil & rock	8	lime	815	1 1/4 BW per hr	1850'
lime	12	shale	819	sdv shale	1862
rock	15	lime	832	water sand HFW	1910
shale lgt	40	slate black	840	sdv lime hrd	1925
shale drk	45	lime	844	shale break	1927
lime	55	slate	870	lime	1943
slate	75	lime	875	shale lgt	1946
lime	85	slate	895	lime	1960
slate	96	water sand	915	lgt sdv shale	1980
lime	100	sdv shale	925	sand	1995
slate muddy	165	sand	940	sdv shale	2020
lime	170	shale gray	950	lime	2050
slate	225	lime	958	slate black	2087
1/2 BW per hr.		slate gray	1020	lime	2098
sand	235	lime hrd	1028	slate black	2115
slate	260	slate gray	1035	lime	2120
lime	265	sdv lime	1055	sand	2125
slate gray	295	shale white & green	1070	white sdv shale	2130
lime	300	red rock	1078	sand	2147
slate	320	lime	1085	shale	2194
lime	325	shale pink & blue	1092	lime	2218
shale drk	350	lime	1102	shale	2231
lime	355	slate blue	1108	brk sand	2240
shale lgt gray	370	lime	1120	lime brk	2255
shale drk	385	slate gray drk	1125	shale	2275
lime shell	388	slate blue	1130	lime	2315
shale gray	395	lime	1135	sdv shale	2322
lime	415	shale	1142	lime	2330
slate	420	Set 10" at 1187'		sdv shale	2455
lime	430	lime	1152		
slate	465	shale blue & pin,	1185		
lime	467	lime	1188		
slate gray	485	slate blue	1205	slate blue	2540
lime	510	sdv gray shale	1225	red rock	2550
slate	525	1 1/2 BW per hr 1225-1240'		shale	2615
lime	529	sand	1240	red rock	2628
slate	538	shale gray	1265	shale blue	2634
red rock	543	lime	1271		
slate	550	shale gray	1352	lime	3023
lime	554	lime	1360	shale black	3035
slate	560	shale gray	1390	sand HFW	3042
lime	565	sand	1400		
lt. gray shale	600	shale gray	1410	Total Depth	3042'
red rock	664	HFW 1420'		Set 6 5/8" csg	2196'
lime	685	water sand	1440	2217' of 6 5/8" csg. in	
shale gray	695	1448 caving		hole	
lime	701	shale	1448	HFW from 3035 to 3042'	
shale gray	705	sand	1475		
lime	724	shale	1558		
shale break	726	lime	1593		
lime	742	sdv lime	1598		
shale	750	shale gray	1630		
lime	754	shale drk	1650		
blk slate	760	shale gray	1768		
red rock	770	gas sand	1778		
Hole caving		1/2 million gas			
lime	785	sand	1790		
slate blue	805	sand showing oil	1807		
lime shell	807	sand	1821		
shale break	809	sand water show	1850		