

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 191 — 20,949
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

1

Lease Name

RUSK "C"

Footage Location

760 feet from (S) (S) line 1980 feet from (E) (E) line

Principal Contractor

Brandt Drilling Company

Geologist

Spud Date

8/30/79

Date Completed

9/16/79

Total Depth

4250'

P.B.T.D.

Directional Deviation


1-1/8 deg @ 3804'

Oil and/or Gas Purchaser

S. 7 T. 33S R. 1 E

Loc. 760' FSL & 1980' FEL

County Sumner

640 Acres
N

Locate well correctly

Elev.: Gr. 1209'

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	322	Common	300	3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
Dry Hole	
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	bbls. MCF
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Driller's Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name RUSK "C"	DRY HOLE
S 7 T 33S R 1 E XX		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			LOGS:	
			Schlumberger	
Soil	0'	5'	DIL w/SFL	1600-4249'
Red Rock	5'	20'	FDC/CNL/GR	323-4243'
Shale & Shaley Lime	20'	180'		
Lime & Shale	180'	655'		
Lime	655'	935'		
Red Rock	935'	980'		
Lime & Sandy Lime	980'	1090'		
Lime & Shale	1090'	1480'		
Lime	1480'	1510'		
Shale w/lime stks.	1510'	1780'		
Lime	1780'	2490'		
Lime & Shale	2490'	2760'		
Lime & Sandy Lime	2760'	3500'		
Sand	3500'	3550'		
Lime	3550'	3875'		
Shale & Red Rock	3875'	3975'		
Sand & Shale	3975'	4055'		
Lime & Cherty Lime	4055'	4110'		
Lime & Sandy Lime	4110'	4250'		
RTD	4250'			
DST #1 3792-3804 (Miss), op 30, SI 30, POH spring broke on tool, rec 95' DM-N.S., IFP 25-36, ISIP 1227 (30), HP 1874-1874.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature Paul Campbell, Division Production Manager Title September 26, 1979 Date
---------------	---

582945

WICHITA BRANCH
Anadarko Production Company

5-33-15