

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


27-33-1E

Company- ROCKET DRILLING COMPANY ET AL
Farm- George No. 1

SEC. 27 T. 33 R. 1E
NE SW SE

Total Depth. 4065
Comm. 11-13-53 Comp. 12-1-53
Shot or Treated.
Contractor. Earl Wakefield
Issued. 3-6-54

County Sumner KANSAS



CASING:

8 5/8" 155' cem. w/100 sx

Elevation. 1277 RB

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	800	DST: 3032-79' open 1 hr.
shale & sandy lime	910	rec. 960' salt wtr.
shale & shells	1165	BHP 1170#.
lime & sandy shale	1364	DST: 3619-23' open 1 1/2 hrs.
shale & sandy lime	1490	rec. 720' of gas & 90' fluid
shale	1506	(15' clean oil, 15' HOCM,
sand & shale	1570	30' watery OCM, & 30' salt
lime & shale	1666	wtr), BHP 1298#.
sand	1680	DST: 3800-3820' open 1 hr.
sand & sandy shale	1696	rec. 605' mud; BHP 695#
shale & lime	1816	DST: 3966-70' open 1 hr.
sand & shale	1845	rec. 20' mud. BHP 1380#.
shale & lime	2596	DST: 3967-77' open 1 hr.
shale & sand	2670	rec. 20' mud, BHP 1360#.
sand & shale	2795	DST: 3999-4021' open 1 hr.
shale & lime	2938	rec. 5' mud, BHP 330#.
shale	3030	DST: 3999-4052' open 1 hour,
shale & sand	3079	rec. 30' mud; BHP 780#.
sand & lime	3124	
shale & lime	3578	No electric log made.
sand, shale & chert	3593	
shale & chert	3623	
lime	3627	
chert & lime	3697	
chat	3700	
shale & lime	3721	
lime	3768	
sandy lime & shale	3795	
lime	3810	
chert & lime	3815	
shale & sand	3820	
lime & shale	3915	
lime	3925	
shale	3967	
sand	3970	
shale & sand	4045	
lime	4065 RTD	
Total Depth		

Tops:

Topeka	1878
Heebner	2285
Toronto	2344
Stalnaker Sand	2622
Layton Zone	3026
Layton Sand	3030
"Lower" Layton Sand	3076
Kansas City (Correlative)	3097
Kansas City Lime	3189
Marmaton Lime	3355
Mississippian	3618
Chattanooga Shale	3929
Simpson Sand	3965
Arbuckle	4045