



# OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

Decmber 15, 1981

Biron, Incorporated  
Box 211  
910 West Elm  
Chanute, Kansas 66720

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Call Lease, Well No. AX-8, located in Section 20, T-33S, R-10E, in Chautauqua County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on December 14, 1981.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/mkf

5 c to Chanute, Ks.

- REGISTERED ENGINEERS -

CORE ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

OILFIELD RESEARCH LABORATORIES

LOG

Name Biron, Incorporated Lease Call Well No. AX-8

Depth Interval,  
Feet

Description

WAYSIDE SAND

1598.0 - 1599.0

Grayish brown slightly shaly sandstone.

1599.0 - 1600.0

Light brown sandstone.

1600.0 - 1601.0

Grayish brown slightly shaly sandstone.

1601.0 - 1606.8

Light brown sandstone.

1606.8 - 1609.0

Gray shale.

# Oilfield Research Laboratories

## RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Biron, Incorporated Lease Call Well No. AX-8

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
			WAYSIDE SAND				
1	1598.4	15.0	29	52	81	338	6.3
2	1599.5	15.5	17	60	77	204	16.
3	1600.5	15.2	17	62	79	201	9.4
4	1601.5	14.7	33	54	87	376	12.
5	1602.6	14.9	20	59	79	231	15.
6	1603.5	14.5	25	55	80	281	10.
7	1604.6	15.0	24	53	77	279	39.
8	1605.5	15.1	29	49	78	340	24.
9	1606.4	15.8	18	61	79	221	31.