

2300
2400
2500
2600
2700
2800
2900
3000
3100
3200
3300
3400
3500
3600
3700
3800
3900
4000

Conoco No. 1 Kroth Strat
33S-3E (No. 49)
~~12-235-3E~~
NW-SW-NE
No. Scout Dope!

~~Marian Co.~~
Cowley Co

samples start 2500'

Red & gray sh. black in streaks
sh. is slightly sandy.
streak gray, f.Xln. lst.

Layton SST 2580

80 gray, f.g. sub-angular, micaceous sst
96 sst. as above interbedded with
red & gray sh.

Wait - plot more
SD in this
interval - Clint

85 gray, fusulinidal marl
86 Red & gray sh.

K.C. 2750

60 gray, f.Xln. fusulinidal lst.
72 gray to brn. f.Xln. lst.
80 black sh. buff, f.Xln. lst.
85 gray to buff, f.Xln. lst.
75 Red & gray sh.

80 dk. gray sh.
82 gray, dsc. to f.Xln. lst. interbedded
with med to dk gray sh.

50 gray to buff, f.Xln. lst.
52 cream to gray, dsc. to f.Xln. lst.
64 Red & gray, slightly sandy sh.

45 gray, dsc. to f.Xln. lst. slightly porous
& oolitic at top
60 black sh.
65 brown, f.Xln. lst.
70 Red & gray sh. interbedded with
gray, f.Xln. lst.

17 black sh.
20 gray, f.Xln. lst.
30 dk. gray sh.
35 gray, f.Xln. lst.
60 Red & gray, sandy sh.
partly

57 buff, f.g. sub-angular, micaceous sst
62 spots dead oil-staining
Red & gray sh. with thin beds gray-
buff, f.Xln. lst.

20 gray, slightly sandy micaceous sh.
37 gray, f.g. tight, silty, sub-angular
micaceous sst. shaley in streaks

58 Mississippian 3258
gray, opaque chert.

79 Samples to 3279 T.D.?

Clint: Wish you
could get some scout
dope on this one

put on a few tops:
where they start
near the bottom of
the section - I can't

be sure where I
am with no near
by control.

They cored from
3220 to 79 &
left very little
in the cuttings.

I may be off several
feet on the Miss.