

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 019 — 22,233
County Number

Operator

WELLS-BATTELSTEIN OIL & GAS, INC.

Address

17 S. ASHBY P.O. BOX 762 CHANUTE, KANSAS 66720

Well No.

#20

Lease Name

GOFF

Footage Location

990' FE & SL NE $\frac{1}{4}$

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

WHITE HAWK DRILLING, INC.

Geologist

N.A.

Spud Date

1-16-81

Date Completed

1-21-81

Total Depth

1130'

P.B.T.D.

Directional Deviation


Oil and/or Gas Purchaser

OKC

County CHAUTAUQUA

640 Acres

N



Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
PRODUCTION	6 $\frac{1}{4}$	4 $\frac{1}{2}$		1127.05'			NONE
SURFACE CASING	9 7/8	7 5/8		92'			NONE

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

WELLS-BATTELSTEIN OIL & GAS, INC.

Well No.

#20

Lease Name

GOFF

32-33-13E

S 32 T 33 R 13 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay	0	24		
Lime	24	27		
Sandstone	27	28		
Shale	28	36		
White Sand	36	39		
Shale	39	94		
Shale	94	276		
Lime	276	282		
Sand	282	287		
Shale	287	304		
Lime	304	307		
Shale	307	358		
Lime	358	375		
Sandy Shale	375	400		
Shale	400	412		
Lime	412	414		
Shale	414	418		
Lime	518	521		
Shale	521	643		
Sandy Shale	643	666		
Shale	666	713		
Lime	713	719		
Shale	719	800		
Shale	800	922		
LENAPAH LIME	922	935		
Sand	935	944		
Shale	944	980		
ALTAMONT LIME	980	998		
Sand	998	1005		
Lime	1005	1014		
Shale Break	1014	1034		
WEISER SAND (GOOD SHOW & ODOR.)	1034	1049		
Water Sand No Show Or Odor	1049	1085		
Water Sand	1085	1087		
Sandy Shale	1087	1130'	T.D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

J. L. HAIGLER
General ManagerC. HUTINETT
Field Superintendent

Signature

Title

Date