



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

October 22, 1980

R.W. Warner
Box 769
Buffalo, Missouri 65627

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Greer Lease, Well No. 9, located in Section 1, T-33S, R-14E, Montgomery County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on October 20, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/tem

3 c to Buffalo, Missouri
1 c to Independence, Missouri
2 c to Coffeyville, Kansas

OILFIELD RESEARCH LABORATORIES

LOGName R.W. Warner Lease Greer Well No. 9Depth Interval,
FeetDescriptionBARTLESVILLE SAND

1162.0 - 1164.1	Grayish light brown very shaly sandstone.
1164.1 - 1168.3	Brown slightly calcareous shaly sandstone.
1168.3 - 1170.0	Brown slightly calcareous sandstone.
1170.0 - 1172.7	Brown slightly calcareous shaly sandstone.
1172.7 - 1175.2	Brown slightly calcareous very shaly sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company R.W. Warner Lease Greer Well No. 9

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	1163.5	15.0	35	46	81	407	0.18
2	1164.5	16.0	43	40	83	534	2.9
3	1165.5	16.2	45	41	86	566	2.2
4	1166.5	14.6	38	52	90	430	2.8
5	1167.5	15.0	48	41	89	559	4.5
6	1168.5	10.1	53	42	95	415	15.
7	1169.5	17.8	41	37	78	566	14.
8	1170.5	16.7	43	35	78	557	5.0
9	1171.5	15.8	59	20	79	723	4.6
10	1172.5	16.5	62	22	84	794	1.3
11	1173.5	16.9	54	23	77	708	0.44
12	1174.5	21.6	47	21	68	788	0.31