

15-125-21592
32-33-14E

S. 32 T. 33S R. 14 E
Loc. SE NE SE
County Montgomery

API No. 15 _____
County _____ Number _____

Operator
Layton Oil Company

Address
Box 263, Independence, KS 67301


Well No. L-24 Lease Name Mitchell

Footage Location
1020 feet from (N) line 220 feet from (E) line SE/4

Principal Contractor Layton Oil Company Geologist _____

Spud Date 11-18-77 Total Depth 722 P.B.T.D. 720'

Date Completed 12-6-77 Oil Purchaser General Energy



640 Acres
N
Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	7 7/8"	7"		23'	Portland	4	5# Cal. Chlor.
Production	6 1/2"	4 1/2"		720'	Portland	110	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	3 1/2 Strap Jet	665-681

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2400# sand and 80 barrels gelled water used to frac	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbis.	MCF	bbis.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 664-682		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Layton Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. L-24 Lease Name Mitchell Oil

S 32 T 33 R 14 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	2		
Clay	2	17		
Shale	17	32		
Hd Sand and Lime	32	37		
Sandy Shale	37	38		
Hd Sand and Lime	38	46		
Sand	46	50		
Sand and Lime	50	56		
Sandy Shale	56	58		
Hd Sand and Lime	58	64		
Sandy Shale	64	187		
Lime	187	195		
Sandy Shale	195	216		
Sandy Lime	216	219		
Sand and Shale	219	402		
Sand and Lime	402	415		
Sandy Shale	415	437		
Sand and Shale	437	460		
Lime	460	471		
Sand and Shale	471	649		
Lime	649	663		
Oil sandy Shale	663	668		
Lime and Shale	668	669		
Oil Sand (Wayside)	669	691		
Sand and Shale	691	722		
	722 TD			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>M. E. Wohltman</i>
	Signature
	Engineer
	Title
	11-18-78
	Date

33-100