


DESCRIPTION OF WELL AND LEASE

Designate Type of Completion

WELL HISTORY

Section Plat



WATER SUPPLY INFORMATION

SIDE TWO

Operator Name OK Discoveries, Inc. Lease Name Clarkson Well # 1
 Sec. 27 Twp. 33 Rge. 15 ☐ East ☐ West County Montgomery

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rate if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☐ No
 Samples Sent to Geological Survey ☐ Yes ☐ No
 Cores Taken ☐ Yes ☐ No

Formation Description
☒ Log ☐ Sample

Core # 1 467-484

Name	Top	Bottom
Peru	712	728

Core # 2 712-732

350 PSI Shut in

1985

	Oil	Gas	Water	Gas-Oil Ratio	Gravity
Estimated Production Per 24 Hours	2 Bbls	Not measurable MCF	2 Bbls	CFPB	32

METHOD OF COMPLETION

Production Interval

Disposition of gas: ☐ Vented ☐ Sold ☐ Used on Lease

☐ Open Hole ☒ Perforation
☐ Other (Specify) alternate 2

CASING RECORD ☐ New ☒ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	8 3/4	6 1/2	17	20.10	Portland	10	4% cal.
Production	5 1/4	2 7/8	6.5	780	Portland	85	Service Co.

PERFORATION RECORD

Shots Per Foot	Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2 SPF	706 to 711 5ft. 11 shots	Fracture 10 sax 10-30	706
	714 to 722 8ft. 17 shots	70 sax 10-30	722
	725 to 728 3ft. 7 shots		728
		180 bbl gelled salt water + clay	

TUBING RECORD	Size	Set At	Packer at	Liner Run	☐ Yes ☒ No
	1"	742			

Date of First Production 9-27-84 Producing Method ☐ Flowing ☒ Pumping ☐ Gas Lift ☐ Other (explain).....