



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

June 13, 1979

Diamond Oil Producers, Inc.
114 South Depot
Cherryvale, Kansas 67335

Gentlemen:

Enclosed herewith are the results of tests run on the rotary core taken from the Mattox Lease, Well No. 3, Labette County, Kansas, and submitted to our laboratory on June 11, 1979.

The core was sampled and sealed in plastic bags by a representative of the client.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Benjamin R. Pearman
Benjamin R. Pearman

SAM:km
5 c to Cherryvale, Kansas

Oilfield Research Laboratories

GENERAL INFORMATION & SUMMARY

Company Diamond Oil Producers, Inc. Lease Mattox Well No. 3

Location From SW Corner - 1,815' EWL & 1,815' NSL

Section 6 Twp. 33S Rge. 18E County Labette State Kansas

Name of Sand - - - - - Lower Bartlesville

Top of Core - - - - - 676.0

Bottom of Core - - - - - 682.0

Top of Sand - - - - - 676.0

Bottom of Sand - - - - - 682.0

Total Feet of Permeable Sand - - - - - 3.6

Total Feet of Floodable Sand - - - - -

Distribution of Permeable Sand:
Permeability Range
Millidarcys

Feet

Cum. Ft.

0 - 1

1.6

1.6

1 - 20

2.0

3.6

Average Permeability Millidarcys - - - - - 4.5

Average Percent Porosity - - - - - 12.6

Average Percent Oil Saturation - - - - - 31.1

Average Percent Water Saturation - - - - - 56.8

Average Oil Content, Bbls./A. Ft. - - - - - 315.

Total Oil Content, Bbls./Acre - - - - - 1,891.

Average Percent Oil Recovery by Laboratory Flooding Tests - - - - -

Average Oil Recovery by Laboratory Flooding Tests, Bbls./A. Ft. - - - - -

Total Oil Recovery by Laboratory Flooding Tests, Bbls./Acre - - - - -

Total Calculated Oil Recovery, Bbls./Acre - - - - -

Packer Setting, Feet - - - - -

Viscosity, Centipoises @ - - - - -

A. P. I. Gravity, degrees @ 60 °F - - - - -

Elevation, Feet - - - - -

OILFIELD RESEARCH LABORATORIES

LOG

Name Diamond Oil Producers, Inc. Lease Mattox Well No. 3

<u>Depth Interval, Feet</u>	<u>Description</u>
676.0 - 679.6	Dark brown shaly sandstone.
679.6 - 682.0	Gray and light brown laminated shaly sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1-B

Company Diamond Oil Producers, Inc. Lease Mattox Well No. 3

Sample No.	Depth, Feet	Effective Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.	Feet of Sand		Total Oil Content	Perm. Capacity Ft. X md.
			Oil	Water	Total			Ft.	Cum. Ft.		
1	676.5	14.5	46	33	79	518	0.65	1.0	1.0	518	0.65
2	677.6	11.1	44	52	96	379	13.	1.0	2.0	379	13.00
3	678.4	16.4	39	32	71	496	2.5	1.0	3.0	496	2.50
4	679.4	10.9	48	48	96	406	0.16	0.6	3.6	244	0.10
5	680.5	11.8	14	82	96	128	Imp.	1.4	5.0	179	0.00
6	681.5	10.8	9	80	89	75	Imp.	1.0	6.0	75	0.00

Oilfield Research Laboratories

SUMMARY OF PERMEABILITY & SATURATION TESTS

TABLE III

Company	Diamond Oil Producers, Inc.		Lease	Mattox	Well No.	3
Depth Interval, Feet	Depth Interval, Feet	Feet of Core Analyzed	Average Permeability, Millidarcys	Permeability Capacity Ft. x Md.		
676.0 - 682.0	676.0 - 682.0	3.6	4.5	16.25		
Depth Interval, Feet	Feet of Core Analyzed	Average Percent Porosity	Average Percent Oil Saturation	Average Percent Water Saturation	Average Oil Content Bbl./A. Ft.	Total Oil Content Bbls./Acre
676.0 - 682.0	6.0	12.6	31.1	56.8	315	1,891