

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

21-33-4E


Company- BEDELL-CATT DRIG. CO. 2
Farm- Muret No.

SEC. 21 T. 33 R. 4E
SE NW SE

NE SW SE - ?

County Cowley
KANSAS

Total Depth. 3205'
Comm. 4-10-57 Comp. 4-19-57
Shot or Treated.
Contractor. Bedell-Catt Drig. Co.
Issued. 9-21-57



CASING:

8 5/8" 130' w/150 sx cem.
4 1/2" 3205'

Elevation. 1153' R.B.

Production. 25 BOPD

Figures indicate Bottom of Formations.

surface hole	130
lime-shale	1670
lime	1756
lime-shale	2435
shale	2460
lime-sand	2585
shale	2640
lime-shale	2720
lime	2743
sand-shale	2846
shale-lime	2940
B. sand	2954
shale-lime	3163
Mississippi chat	3205
Total Depth	

TOPS: Scout	
U. Layton	2457
L. Layton	2524
Kansas City=	2634
Cleveland	2743
Ft. Scott	2877
Cherokee	2941
Mississippi	3164