

Geological Survey
WICHITA, BRANCH
WELL COMPLETION REPORT AND
DRILLER'S LOG

KANSAS

22-33-4E

S. 22 T. 33S R. 4 E

Loc. C SW NW

County Cowley

API No. 15 — 035 — 22332 ✓
County Number

Operator
Range Oil Company, Inc.

Address
240 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Well No. 5 Lease Name Meadows "B"

Footage Log

Principal Con

Spud Date

Directional D

STATE KANSAS 12-4-58 MAP NO. S-T-R 22-33S-4E D
OPER RANGE OIL CO SPOT C SW NW INIT
220 W DOUGLAS WICHITA KS CO COWLEY DO
WELL 5 MEADOWS "B" ELEV 1190 KB FIN
CONTR OWN
FIELD POSEY NE (MISS)

IP IPP 15 BOPD + WTR, MISS 3186-3210 OA
API 15-035-22332 FR 9-11-79

SPUD 9-28-79, w/spdr, 8 5/8" @230 w/90, Geol S Kreidler
DST 1 (NEVA/ADM) 700-750, op30, si30, op60, si30,
GTS/NT, 2nd Op: F 5.3 MCFG & stab, Rec 150' Mud,
ISIP 204, FP 107-96/129-118, FSIP 247, BHT 77
RTD 3248 (10-11-79), 4 1/2" @ 3247 w/75
Perf (MISS) 3186-97 & 3203-10, 2500 Gal 15% A,
fract w/957 BAW + 35,000 sd

IPP 15 BOPD + WTR, MISS 3186-3210 OA
COMPLETED 11-30-79

Top, ft.

KB LOG TOPS:

NEVA 480 + 710
ADMIRE SD 712 + 478
LATAN 2021 - 831
STALNAKER 2050 - 860
PERRY LM 2251 - 1061
PERRY SD 2260 - 1070
HOGSHOOTER 2467 - 1277
LAYTON PORO 2487 - 1297
KANSAS CITY 2622 - 1432
B/KANSAS CITY 2772 - 1582
OSWEGO 2851 - 1661

CHEROKEE

Pi Petroleum Information Corporation
A Subsidiary of A. C. Nielsen Company

(CON'T)

BARTLESVILLE 3146 - 1956
MISS CH 3185 - 1995
MISS LM 3210 - 2020
RTD 3248 - 2058
LTD 3249 - 2059
TD IN MISS

COMP ISSUED 12-26-79

12-4-58

Date of first

RATE OF PI
PER 24 HOURS

Disposition of

INSTRUC

mitted to the State Geological Survey of Kansas, 1700 Kansas
Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note
Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

