

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


28-33-4E

Company- ALBERT WILSON  
Farm- Richardson No. 1

SEC. 28 T. 33 R. 4E  
NE NE NW

Total Depth. 3609'  
Comm. 5-6-58 Comp. 5-18-58  
Shot or Treated.  
Contractor. G. D. Smitherman Drilg. Co.  
Issued. 8-23-58

County Cowley  
KANSAS



CASING:  
8 5/8" @ 206' w/200 sx.

Elevation. 1136' KB

Production. Dry

Figures Indicate Bottom of Formations.

lime & shale	1758
sdv shale & shale	1975
shale & lime	2015
sand & shale	2230
shale & lime	2418
shale & sand	2430
(2423 top of Layton)	
Coring	2446
shale & sand	2610
(2594 top of K.C.)	
lime (KC) shale	2690
shale	2717
coring (sand)	2745
(2715 top of Cleveland)	
coring (sand)	2752
shale & lime	2780
lime (OS)	2810
lime & shale	3134
chat	3154
lime & chert	3212
lime	3218
lime & shale	3609
Total Depth	

Tops:	
Stalaker (Scout)	2015
Layton Sandstone	2423
K. C. Limestone	2594
Cleveland Sandstone	2715
Marmaton Limestone	2780
Cherokee	2886
Mississippi "Chat" - (Cherty Conglomerate)	3126
Mississippi "Chat"	3132
Mississippi Limestone	3162
Kinderhook	3378
Chattanooga Shale	3545
Arbuckle Dolomite	3604

Core #1 2438 - 2447  
Core #2 2717 - 2752

DST #1 - 3133-3141. Open 1 hour, shut  
in 30 min. Rec. 300' gas, 60' oil cut  
mud. BHP 540#