

State Geological Survey

KANSAS DRILLERS LOG

API No. 15 — 035 — 21142
County Number

S. 11 T. 33 R. 5 ^E_W

Loc. _____

County

Operator

Range Oil Company, Inc.

Address

Well Nc

Footage

STATE KANSAS 5-5-82 MAP NO. S-T-8 11-33S-5E D

Principa

OPER	RANGE OIL CO	SPOT	C SW NW	INIT
------	--------------	------	---------	------

240 PAGE CT, 220 W DOUGLAS, WICHITA

Spud De

NAME **MADDIX**  CO **1256 YB**

CONTR. WHITE & ELLIS DRUG

Date C

FIELD MADDIX W (MISS)

IP IPP 30 BOPD + TR WTR. MISS 3081-3102 OA

API 15-035-21142

KB LOG TOPS:

ADMIRE 604 + 652

STALNAKER 1890 - 634

LAYTON 2332 - 1076

KANSAS CITY 2472 - 1216

B/KANSAS CITY 2622 - 1366

OSWEGO 2696 - 1440

CHEROKEE 2824 - 1568

MISS 3076 - 1820

LTD 3/28 (-1072) 3125 - 1869

RTD 3143 - 1887

TD IN MISS

COMP ISSUED 5-30-77

P₁™ Petroleum Information

^c Copyrighted 1977. Reproduction Prohibited

Top. ft.

Depth interval

Size

interval treated

ratio

CFPB

rs Log shall be trans-
from the Conservation
of confidential custody
sas, Lawrence, Kansas

C-10-1972

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No.	Lease Name		
S _____ T _____ R _____ E _____ W _____			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
DEPTH			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	Range Oil Company, Inc. _____ Signature Robert G. Brooks _____ Title Geologist _____ Date		

001002

DRILLERS LOG

15-035-21142

11-33-5E

OPERATOR: Range Oil Company; 240 Page Court; 220 W. Douglas; Wichita, KS 67202
CONTRACTOR: **White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042**

Lease Name Maddix Well No. 2

Sec. 11 T. 33S R. 5E Spot C SW NW

County Cowley State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 160' with 85 Sxs.

Production: 4 1/2" @ 3139' with 75 Sxs.

Type Well: Oil Total Depth 3140' K.B.

Drilling Commenced: 3-30-77 Drilling Completed 4-4-77

Formation	From	To	Tops
Cellar	0	7	Kansas City 2455
Lime & Shale (Stks)	7	625	Cleveland 2632
Shale	625	700	Mississippi 3095
Shale & Lime (Stks)	700	1634	
Shale & Sand	1634	1859	
Lime	1859	1863	
Sand & Shale	1863	2040	
Sandy Shale	2040	2230	
Shale	2230	2315	
Sand & Shale	2315	2455	
Lime	2455	2625	
Shale	2625	2632	
Sand	2632	2637	
Shale	2637	2708	
Lime	2708	2828	
Shale	2828	3095	
Lime	3095	3140	