

WICHITA BRANCH

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 035 — 22300 ✓
County Number

Operator

Range Oil Company, Inc.

Address

240 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Well No.

10

Lease Name

Maddix

Footage Locatio

Principal Contra

Spud Date

Directional Dev

Report o

Purpose o

Top, ft.

Size

Date of first

RATE OF PF
PER 24 HOI

Disposition o

STATE KANSAS

11-3-71

MAP NO.


S-T-R 11-33S-5E

D

OPER RANGE OIL CO

240 PAGE COURT

WICHITA, KS



SPOT 60' W/C SE SW

INIT

WELL 10 MADDIX

CO COWLEY

DO

CONTR OWN

ELEV 1229 KB

FIN

FIELD MADDIX NE (MISS)

IP IPP 15 BOPD + WTR, MISS 3060-82 OA

API 15-035-22300 FR 8-13-79

SPUD 8-28-79 w/spdr, 8 5/8" @ 168 w/50, Geol
Steve KreidlerDST 1 (NEVA/ADM) 555-85, op30, si30, op35, si30,
GTS/15", stab @ 6720 MCFG, Rec 40' MCW, ISIP
219, FP 62-31/52-31, FSIP 219, BHT 82

RTD 3125 (9-8-79), log: GGD, 4 1/2" @ 3124 w/75

Perf (MISS) 3060-67 & 3072-82, 2,500 Gal 15% A,
fract w/965 BAW + 35,000 sd

IPP 15 BOPD + WTR, MISS 3060-82 OA

COMPLETED 10-31-79

KB LOG TOPS:

NEVA	333 + 896
ADMIRE SD	566 + 663
IATAN	1838 - 609
STALNAKER	1872 - 643
PERRY LM	2067 - 838
PERRY SD	2082 - 853
HOGSHOOTER	2269 - 1040
LAYTON "B"	2318 - 1089
KANSAS CITY	2448 - 1219
B/KANSAS CITY	2604 - 1375
OSWEGO	2680 - 1451

nd percent
ditives

interval

(CON'T)

P Petroleum Information
Corporation

COPYRIGHTED 1979 REPRODUCTION PROHIBITED

CHEROKEE	2805 - 1576
MISS	3057 - 1828
MISS CH	3060 - 1831
MISS LM	3066 - 1837
LTD	3125 - 1896
RTD	3125 - 1896
TD IN MISS	

treated

COMP ISSUED 11-20-79

CFPB

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:		
Well No.	Lease Name			
S _____ T _____ R _____ E _____ W				
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	Robert G. Brooks Signature Vice President of Exploration Title March 27, 1980 Date			

1-33-26