


Company- K. T. WEIDEMANN  
 Farm- S. G. Hammer No. 1

SEC. 5 T. 33 R. 6E  
 SE SE SE

Total Depth. 3532  
 Comm. 9-27-51 Comp. 12-22-51  
 Shot or Treated. 1000 gals. acid  
 Contractor. 6-21-52  
 Issued.

County Cowley  
 KANSAS



CASING:  
 10 3/4" 69' cem. w/75 sx  
 7" oil string 3107' Cem. w/25 sx Pulled  
 5 1/2" oil string 3537' cem. w/no sx Pulled  
 Figures Indicate Bottom of Formations.  
 Ground Level to Rotary Table 5'

Elevation. 1335  
 1337 (Ind)  
 Production. dry

cellar	5
rock & clay	11
lime	77
shale	80
lime & shale	90
lime & shale breaks	174
shale & shells	305
shale & lime streaks	510
shale & lime	575
shale & shells	760
lime & shale streaks	785
shale & shells	968
lime	1020
lime & shale breaks	1318
shale	1400
lime	1470
shale & shells	1650
shale	1661
lime	1684
shale	1890
lime	1905
shale	1950
lime & shale	2040
shale	2094
lime & shale	2210
shale	2320
sandy shale	2365
sand	2425
shale & lime	2495
shale	2543
lime	2635
lime & shale	2715
lime	2764
shale	2800
lime & shale	2940
shale	3103
Miss. chert	3107, RTD
Cable Tools	
lime	3452
shale	3509
dolomite	3532
Total depth	

2850  
 1335  
 -----  
 1515

Tops:  
 Layton S.S. 2315  
 Kansas City lst 2520  
 Marmaton lst 2725  
 Cherokee sh. 2850  
 Miss. chert 3103  
 Base Miss. lime 3452  
 Arbuckle dolomite 3509