

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

29-33-6E ✓

Company- WRICO DRILG., INC., ET AL
Farm- Green No. 2

SEC. 29 T. 33 R. 6E
SW NE NW

Total Depth. 3095'
Comm. 11-3-65 Comp. 11-9-65
Shot or Treated.
Contractor. Co. Tools
Issued. 1-1-66

County Cowley
KANSAS



CASING:
8 5/8" 191' w/135 sx cem.

Elevation. 1279' K.B.

Production. DRY

Figures Indicate Bottom of Formations.

lime	50
lime, shale	191
lime	210
lime, shale	550
shale, shells	780
shale	1160
shale, lime	1875
sand, shale	2050
shale	2248
Layton	2260
sand	2410
shale, Kansas City lime	2515
lime	2595
lime, shale	2885
shale, lime stks	3020
shale	3067
Mississippian	3095
Rotary Total Depth	

TOPS:

Iatan lime	1818
Stalnaker sand	1843
Layton sdy lime	2248
Layton sand	2307
Kansas City sand	2429
Kansas City lime	2458
Marmaton lime	2678
Cherokee shale	2803
Mississippi	3066

DST # 1 - 3067-3084- weak blow
20 min., SI 30 min.; IBHP 99 psi.,
weak bloe for 1½ hrs., Final 30
min. BHP 81 psi., IFP 18 psi.,
FFP 54 psi., Rec. 35' drilling mud
& 33' fairly heavy oil cut mud.