

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

31-33-6E

Company- ROCK HILL OIL & CREST PETROLEUM, INC.
Farm- Berry No. 2

SEC. 31 T. 33 R. 6E
SW SE NE

Total Depth. 2248'

Comm. 1-11-54


Comp. 1-16-54

Shot or Treated.

Contractor. Fortier & Wright Drilling Co.

Issued. 4-3-54

County Cowley
KANSAS



CASING:

8 5/8" 68' cem w/55 sx
5 1/2" 2246' cem w/50 sx

Elevation. 1193 DF

Production. Pump 25 Bbls. &
50 wtr.

Figures Indicate Bottom of Formations.

soil - sub-soil	15
soft lime	45
hard lime	55
soft lime	58
red bed	68
lime-shale-red bed	175
red bed-lime-shale	490
shale - shells	765
shale - lime	1130
lime - sand - shale	1375
lime - shale	1500
shale - sand	1800
sand - shale	1964
shale - sand	2048
shale	2165
sand - shale	2181
sand	2248
Total Depth.	

Core #1 2165 - 2193
sand - shale 2181
Layton sand 2193
Core #2 2193 - 2218
sand 2218

Tops:
Stalnaker Sand 1768
Layton Zone 2158
Layton Sand 2181

Perforated: 2195 - 2200 with 30 shots.

Swabbed: 5 bbls. oil /hr.
10 bbls. water /hr. Put on pump.