

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


31-33-6E

Company- CREST PETROLEUM, INC. & DUKE & WOOD DRLG
Farm- Berry "C" No. 4

SEC. 31 T. 33 R. 6E
NE NE SE

Total Depth. 2185 RB
Comm. 6-8-54 Comp. 6-14-54
Shot or Treated.
Contractor. Fortier & Wright Drlg Co.
Issued. 7-31-54

County Cowley
KANSAS



Elevation. 1070 K.F.

Production. Pump 50 bbls / 30
water

CASING:

8 5/8" 63' cem w/75 sx
5 1/2" 2185' cem w/60 sx

All measurements from rotary
bushing 2 1/2' above Derrick Floor. Figures indicate Bottom of Formations.

lime, shale	35
red bed, shale	68
lime soft	74
shale	79
lime	85
shale	88
lime	110
lime, red bed, shale	115
shale, lime	610
shale, sand, lime	910
shale, lime	1040
shale, sand	1500
lime sdy, shale	1670
shale, lime	1750
sand Stalnaker	1815
shale	1900
sand, shale	2020
shale	2125
shale sandy	2145
CORE No. 1 2145-2185	
Recovered 40'	
sand - Oil	2185
Total Depth	RTD

Tops:
Stalnaker Sand 1748
Layton Zone 2129
Layton Sand 2149'6"

Cable Tools: Logged & perf. 25 holes
2159-2164. Bailed & tested 1 BO & 1 1/2 BW
per hr.
Fractured: Estimated 100 bbla oil & 60
BW per day.