


Company - THE TEXAS COMPANY  
Farm - A. M. Ott No. 1

SEC. 8 T. 33 R. 6 E  
SWE SW

Total Depth. 3582' FB 3330  
Comm. 10-23-44 Comp. 12-15-44  
Shot or Treated.  
Contractor. Helmerich & Payne  
Issued. 1-20-45 Rotary O-3582

County. Cowley  
KANSAS



Elevation. 1305

Production. Dry

CASING:  
10 3/4" 139' Cem.  
5 1/2" 3519' Cem.

Figures Indicate Bottom of Formations.

lime hrd 15  
lime 75  
sand 90  
lime hrd 110  
red bed, shale, lime 130  
lime 180  
lime & shale 230  
lime 245  
red bed 255  
lime 320  
red bed & shells 350  
lime 385  
lime & shale 410  
lime 425  
lime & shale 1225  
lime 1255  
shale & lime 1295  
lime brkn 1370  
sand 1385  
lime & shale 1470  
lime 1490  
shale & lime 1980  
shale & shells 2050  
shale 2090  
sand 2114  
shale 2135  
shale & lime 2225  
shale & shells 2315  
shale, shells & sand 2395  
sdy shale 2405  
shale & shells 2528  
lime 2610  
sdy lime 2630  
shale & lime 2750  
shale 2758  
lime sdy 2890  
lime & shale 2903  
shale 2935  
shale & lime 3016  
shale & lime shells 3066  
shale 3080  
cherty lime 3102  
cherty lime & shale strks 3111  
lime & shale 3120  
shale & lime 3186  
sdy lime 3194  
lime 3224  
shale & lime 3254  
lime 3338  
shale & lime 3350  
lime 3354  
lime & shale 3378  
shale & lime 3385  
shale 3396  
lime & shale 3407  
lime hrd 3450  
shale & cherty lime 3460

shale & lime 3464  
lime 3488  
lime & shale 3518  
shale blk 3525  
lime (arbuckle) 3546  
lime 3582  
Total Depth.

Perf 3074-88' w/29 holes,  
acidized w/500 gals, swbd  
13 1/2 BW & 1/2 B. free oil FH-  
Swbd 36 hrs, unable to  
lower wtr

Tops:  
Lansing 1860  
Stalneker 1942  
Layton 2295  
Base Oswego 2835  
Miss 3074  
Kinderhook 3463  
Chatt 3501  
Arbuckle 3519

Ran Schlumberger on 11-27-44

Plugged back 3350

E