

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
5CS East Murdock, Wichita, Kansas


13-34-1E

Company-LARIO OIL AND GAS CO.
Farm- Williamson "B" No. 1

SEC. 13 T. 34 R. 1E
CW/2 SW SW

Total Depth. 3930', PBTD 3565'
Comm. 12-5-59 Comp. 12-15-59
Shot or Treated.
Contractor. Gabbert-Jones Drlg. Co.
Issued. 1-30-60

County Summer KANSAS



Elevation. 1167 RB

Production. 52 BOPD plus
6% wtr..

CASING:

8 5/8" 254 cem/185 sx.
5 1/2" 3811.53' cem/280 sx.
D.V. Tool at 3252'

Figures indicate Bottom of Formations.

clay & shale	110
anhydrite	150
lime shells	254
lime	800
lime & shale	1785
lime	1935
lime & shale	2040
lime	2190
lime & shale	2310
lime	2385
shale & sand	2515
sand & lime	2585
lime & shale	2885
shale & sand	2950
sand	2995
shale & lime	3180
lime	3250
lime & shale	3435
lime	3636
shale & lime	3669
shale & Simpson sand	3714
sand	3723
shale & lime	3748
shale & sand	3763
lime	3930
Total Depth	
PBTD	3565

Marmaton	3220
Cherokee	3344
Mississippi chert	3484
" lime	3573
Chattanooga shale	3673
Simpson	3701
Basal Simpson sd.	3744
Arbuckle	3764
12-10-59 Welex perf. 24 holes	3748-54.
12-10-59 Acidized 250 Gal. MCA acid.	
12-13-59 Welex perf. 48 holes	3538-45.
Acidized w/500 gal. MCA acid..	
12-14-59 Fraced w/Viso-Frag 4000 gal.	
Jelled crude and 6000# sand.	

TOPS:

Indian Cove SS..	1400
Fuqua zone	1492
White Cloud Ss. zone	1672
Howard	1783
Elgin Sd. zone	1998
Heebner	2130
Iatan	2422
Stalnaker Sd. zone	2442
Top of clean porous sand	2500
Upper Layton Sd. zone	2863
Lower " " "	2930
Kansas City	3041
Base Kansas City	3126
Cleveland sand	3142