

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

Plotted
A.S.

SINCLAIR PRAIRIE OIL COMPANY.
I.J.Cleek No. 39

SEC. 30 T. 34 R. 12E.
SE NW SW NW
600' f NL 440' f WL S $\frac{1}{2}$ NW $\frac{1}{4}$

Total Depth. 1087
Comm. 3-1-40 Comp. 3-21-40
Shot or Treated.
Contractor. Locke Drilling Co.
Issued. 5-31-41

County Chautauqua.

CASING.

103/4" 21'
85/8" 225' All pulled.
7" 900'
2" tubing 1091'

Elevation.

Production. 15 bbls
after shot.

Figures Indicate Bottom of Formations.

clay	30
shale	40
lime	47
shale	105
lime	108
shale	135
lime	140
shale	165
sand	213
shale	408
lime	419
shale	429
lime	452
shale	490
lime	505
sand	515
shale	550
sand	560
shale	662
lime	670
shale	740
sand	820
lime	825
shale	845
lime	858
shale	862
sand	881
shale	895
shale	1034
lime	1050
sand	1062
shale	1087

Total Depth.

Peru sand 1050-1060

Shot 40 qts in 12' of 4 $\frac{1}{2}$ shell between 1050-62

Pumping on Jack.

1st 24 hours Nat. Prod. 7 bbls.,
1st 24 hours after shot 15 bbls.,
2nd 24 hours after shot 8 bbls.,

