


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

SINCLAIR PRAIRIE OIL CO.  
Geo. Bowen No. 24.

SEC. 19 T. 34 R. 12 E  
NE SE SE NE  
885'f NL 150'f EL(S $\frac{1}{2}$  NE $\frac{1}{4}$  ?)

Total Depth. 1016'  
Comm. 2-8-43 Comp. 2-25-43  
Shot or Treated. 60 Qts. 2-22-43 978-90  
Contractor. Bennett Drlg. Co.  
Issued. 3-13-43

County. Chautauqua



CASING:

10 $\frac{3}{4}$ " 29' LI  
7" 826' LI  
2" 1019' LI

Elevation.

Production. 8 B.

Figures Indicate Bottom of Formations.

|                |                    |
|----------------|--------------------|
| quick sand     | 30                 |
| shale          | 53                 |
| sand           | 75                 |
| shale          | 110                |
| sand           | 116                |
| shale sdy      | 125                |
| shale          | 348 <i>top P15</i> |
| lime           | 355                |
| shale          | 390                |
| lime           | 392                |
| sand           | 450                |
| shale          | 608                |
| lime blk       | 612                |
| shale          | 650                |
| sand(Big Salt) | 730                |
| shale          | 760                |
| lime           | 765                |
| shale          | 781                |
| sand           | 799                |
| shale          | 955                |
| shale dk       | 961                |
| lime           | 964                |
| shale          | 969                |
| lime           | 976                |
| sand           | 990                |
| shale          | 1016               |
| Total Depth.   |                    |

Reduced hole at 336

Peru sand 976-90