

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

PLOTTED  
G. E. Jameson

SINCLAIR PRAIRIE OIL CO.  
Hartzell No. 19

SEC. 19 T. 34 R. 12E.  
NW SE SE  
1240' fr SL 950' EL of SE $\frac{1}{4}$


Total Depth. 1043  
Comm. 11-24-37 Comp. 12-13-37  
Shot or Treated. 40 qts 1002-1020  
Contractor.  
Issued. 2-12-38

County Chautauqua.

FEB 12 1938

CASING.

103/4"	27'
85/8"	150'
7"	848'
2"	1015'



Elevation.

Production. Pot. 8 B.

Figures Indicate Bottom of Formations.

sdv soil	8
river gravel	15
sdv shale	40
shale	85
sand	90
sand	135
shale	375
lime	385
shale	387
sand	397
shale	430
sand	480
shale	625
lime	630
shale	670
sand	700
shale	705
sand	747
shale	796
lime	805
shale blk	811
lime	814
sand	821
shale	825
sand	840
shale	980
lime	983
shale	985
lime	1001
Peru sand	1020
shale	1043

Total Depth.

Peru sand 1001-1020