


Company - SINCLAIR PRAIRIE OIL CO.
Farm - A. L. Hertzell No. 24

SEC. 19 T. 34 R. 12 E
SW NE SW
1723' fSL & 1055' fEL SW

Total Depth 1040'
Comm. 7-20-46 Comp. 8-8-46
Shot or Treated.
Contractor. Bennett Drlg. Co.
Issued. 10-12-46

County. Chautauqua
KANSAS



CASING:
11" 24' 2" 1043'
8 5/8" 476' P
7" 852'

Elevation. _____

Production. 15 BO, 2nd 24 hrs.
after shot.

Figures Indicate Bottom of Formations.

soil	10
quicksand	20
shale	55
lime	63
sand	71
shale	73
lime	100
sand	113
shale sdy	115
shale	120
sand	125
shale	370
sand	378
shale	423
sand	471
shale	596
lime shells	600
shale lgt	615
shale drk	626
lime	630
shale	684
sand salt	750
shale	790
sand	815
shale	818
sand	830
shale	832
sand brkn	836
shale lgt	844
shale	949
shale lgt	963
shale drk	973
lime	977
shale lgt	982
lime	997
sand Peru	1014 SLM
shale	1040
Total Depth.	

Peru Sand 997-1014'

Shot between 997-1014' w/60 qts.

Water sand from 63-71' 3/4" Bailers
per hr.

Water from 684-750' HFW.

Prod. 1st 24 hrs. 30 BO

Prod. 2nd 24 hrs. after shot 15 BO.