

15-34-12E

Operator JOHN M. DENMAN OIL CO.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 7

Lease Name J. C. Conley

Oil

S 15 T 34 R 12 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Log Attached				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Signature

Title

Date

15-34-12E

State Geological Survey
WICHITA, KANSAS

API# 15-019-20, 356

JOHN M. DUNNAN OIL CO.

WELL LOG OF J.C. CONLEY LEASE, WELL # 7, NE1/4 15-34-12 CHAUTAUKA COUNTY, KANSAS

DRILLING STARTED 7-7-73

WELL COMPLETED 9-24-73



<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	15	
Shale	15	124	21' of surface pipe
Lime	124	143	
Shale	143	389	
Lime	389	400	Put on jars
Shale	400	436	
H-up	436	466	4 BW per hr @ 435°. Crooked hole. Plug. Drill
Shale	466	484	477' of 8"
Lime	484	486	
Shale	486	508	Little water @ 515'
Sand	508	543	10 BW per hr @ 530'
Shale	543	627	
Sand	627	641	HFV 632-660'
Shale	641	648	
Sand	648	667	16 BW per hr
Shale	667	732	Cut off 150' drill line
Sand	732	747	
Shale	747	820	Cut off 325' of Sand line
Lime	820	828	
Shale	828	831	
Sand	831	859	
Shale	859	886	Ran 882' of 7"
Sand	886	897	
Shale	897	1019	Pipe settled 4 1/2', dry at noon
Falsc cap rock	1019	1021	5 gal water in hole this AM
Shale	1021	1025	
Lime-Peru cap	1025	1035	
Sand	1035	1048	Started core @ 1047
Shale	1048	1067	Overnite-5 gal water, some oil
Sand	1067	1068	
Shale	1068	1077	
Sand	1077	1092	30 Min test-4 gal water, 1 Qt oil
Shale	1092	1097	
Lime	1097	1100	Overnite, 16 hrs-18 gal oil, 2 gal water

9-14-73- Ran 1100' of 4", Palled 7"
Cemented 4" w/25 sacks- Consolidated

9-17-73- Palled 8". Cemented 21' of 8" surface, strung up 4" tools

9-18-73- Perf from 1043-1048 W/6 shots
Perf from 1077-1090 W/14 shots
Swabbed hole & bailed dry

9-19-73- Frac by Dowell

9-20-73- Well on vacuum at 7:30 AM. 5' sand in hole.

9-21-73- Clean out

9-24-73- Ran 1080' of upset tube, 12' of perf & mud anchor, 5' bbl, 3' off bottom
43 5/8" rods w/15/16 pins, 8' pony