


SINCLAIR PRAIRIE OIL CO.
 Mike DeArmond No. 21.

SEC. 15 T. 34 R. 12 E
 SW NE SW NW
 720' f SL 700' f WL S $\frac{1}{2}$ NW $\frac{1}{2}$

Total Depth. 982'
 Comm. 6-28-43 Comp. 7-20-43
 Shot or Treated. 70 Qts. 930-58 7-10-43
 Contractor. Bennett Drlg. Co.
 Issued. 8-21-43

County. Chautauqua



CASING:

11"	20' LI
8 5/8"	382' P
7"	800' LI

Elevation.

Production. 10 B.

Figures Indicate Bottom of Formations.

after shot

soil	2
clay	6
gravel	15
sand	30
shale	75
shale sdy	125
shale	205
sand	220
shale	284
lime	288
sand	310
shale	346
sand	358
shale sdy	382
shale	395
shale sdy	493
shale	520
shale sdy	560
shale lgt	595
shale	620
sand	690
lime	694
shale sdy	723
shale	732
sand	750
shale	910
lime	912
shale	917
lime	930
sand	938
shale sdy	946
sand	958
shale	982
Total Depth.	

Peru sand 930-58

water 288-310 rises within

200' top of hole

water 620-90

HPW 732-60