


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-34-12E

Company- SINCLAIR PRAIRIE OIL CO.
Farm- Mike DeArmond No. 22

SEC. 15 T. 34 R. 12E
NE NW SE NW
110' frm NL, 400' frm WL
SE $\frac{1}{2}$ NW $\frac{1}{2}$
County Chautauqua
KANSAS

Total Depth. 966
Comm. 11-8-50 Comp. 11-16-50
Shot or Treated.
Contractor. Bennett Drlg Co.
Issued. 3-16-57



Elevation. _____

Production. Bailing 10 bbls

Figures Indicate Bottom of Formations.

CASING:
10 3/4" 79'
8 5/8" 459' P.
5 1/2" 61'
5 1/2" 969'
5/8" sucker rods 925'

soil	8
clay	15
reiver sand, gravel	64
shale	178
sand	210
shale	255
sand	260
shale	315
sand	335
shale	385
sand	415
shale sandy	440
shale	500
shale sandy	595
sand	630
shale	650
shale sandy	700
sand	740
shale	890
lime	910
shale sandy	934
sand {Peru}	951
shale	966

Sand Record:
Peru sand 934-951

Used Tamp shot w/40' cruched rock.
Shot went off at 5:05 p.m. 11-16-50
Used Bolshevik Time Bomb & Combination
Cave Catcher.
Shot w/34 qts between 934-951

No electricl log made

No bottom hole pressure tests.

Cores: none