

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SINCLAIR PRAIRIE OIL CO.
Farm - H. W. Moore No. 20

SEC. 22 T. 34 R. 12E
SE SW NW
100' fr EL, 300' fr SL of
S. NW
County. Chautauqua
KANSAS

Total Depth. 1031
Comm. 10-15-48 Comp. 10-31-48
Shot or Treated. Shot
Contractor. Bennett Drlg. Co.
Issued. 1-22-49

CASING:

11" 27' LI
7" 619' L'
2" 1011' LI
5/8" sucker rods

Elevation. _____

Production. 2nd 24 hrs after shot,
5 bbls.

Figures Indicate Bottom of Formations.

clay	15
shale	30
lime	38
shale	45
sand, hrd	70
shale	80
sand	105
shale sdy	125
sand	132
shale, sdy	155
shale	310
sand	320
shale	358
sand	378
shale sdy	385
sand	422
shale	445
shale sdy	510
shale blk	530
shale	565
sand	590
shale	645
sand	720
shale	770
sand	790
shale	952
li e	955
shale	958
lime	969
sand	975
shale sdy	989
sand	1000
shale	1031
total depth	

PRODUCING FORMATIONS:

Peru Sand, 969-75.
Peru Sand, 969-1000, shot
between.

Larkio Torpedo Co., 11' of
5" shell, 40 quarts. Good
results.

CONDITION OF WELL AT COMPLETION:

1/2 BHPH @ 125'
Reduced hole @ 435'
HFW @ 565'
Run Steel Line @ 811'
Run Steel Line @ 971'.

Present condition of well:
GOOD.