

15-125-22,102

**KANSAS DRILLERS LOG**

API No. 15 — 125 — 22,102  
County Number

Operator Layton Oil Company

Address Box 263, Independence, KS 67301

Well No. X-50 Lease Name Gullick

Footage Location 330 feet from ~~XX~~ (S) line 220 feet from ~~E~~ (W) line NW/4

Principal Contractor Layton Oil Company Geologist \_\_\_\_\_


Spud Date 3-29-79 Total Depth 720 P.B.T.D. 714

Date Completed 6-6-79 Oil Purchaser Producers Group Inc.

S. 3 T. 34S R. 14E W

Loc. SW SW NW

County Montgomery



Locate well correctly

Elev.: Gr. \_\_\_\_\_

DF \_\_\_\_\_ KB \_\_\_\_\_

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	11"	8 5/8"		21	Portland	5	
Production	6 1/2"	4 1/2"		714	Portland	87	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3 1/2" alum. jet	702-780

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Fraced with 1300# coarse sand and 200# fine sand and 140 barrels jelled water.	772-780

**INITIAL PRODUCTION**

Date of first production _____	Producing method (flowing, pumping, gas lift, etc.) _____
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls. Gas _____ MCF Water _____ bbls. Gas-oil ratio _____ CFPB
Disposition of gas (vented, used on lease or sold) _____	Producing interval(s) <u>772-780</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
Layton Oil Comapny

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Well No.  
X-50

Lease Name  
Gullick

Oil

3 34S 14E E  
S T R W

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	3		
Clay	3	8		
Shale	8	10		
Sand	10	28		
Hard Sand and Lime	28	32		
Sand	32	39		
Lime	39	44		
Sand	44	48		
Shale	48	59		
Lime	59	60		
Shale	60	87		
Lime	87	89		
Shale	89	178		
Lime	178	188		
Shale	188	250		
Sand	250	290		
Shale	290	315		
Sand	315	348		
Hard Sand and Lime	348	352		
Sand	352	402		
Shale	402	460		
Lime	460	468		
Sand	468	532		
Shale	532	630		
Lime	630	632		
Shale	632	652		
Lime	652	664		
Sand (Wayside)	664	676		
Broken Sand	676	681		
Sandy Shale	681	720		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Maisha E. Wohltman*

Signature

Assistant

Title

9-28-79

Date