


KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

S. 19 T. 34S R. 14 E

Loc. 1980' FNL 1980' FWL

County Montgomery640 Acres
N

Locate well correctly

Elev.: Gr. 797'.85

DF _____ KB _____

API No. 15 — Montgomery — 15-125-22-901
County Number

Operator

John A. Masek d/b/a/ Masek Oil Company

Address

615 West 11th, Coffeyville, Kansas 67337

Well No.

32-30

Lease Name

Kincaid South

Footage Location

1980 feet from (N) line1980 feet from (W) line

Principal Contractor

Turner-Winter

Geologist

Dennis Wooldridge

Spud Date

1/1/80

Total Depth

1919'

P.B.T.D.

Date Completed

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 3/4"	7"	20#	467' 6"	Regular	150	2% Ca/ Cl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Operator

John A. Masek d/b/a/ Masek Oil Company

Well No.

(1)

Lease Name

Kincaid South

Dry Hole

S 19 T 34 S R 14 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand-Water	272'	333'		272'
Sand	350'	409'		350'
Sand (Moist)	509'	521'		509'
Limestone	706'	721'	Lenepah	706'
Shale	721'	783'		721'
Limestone	783'	832'	Altamont	783'
Limestone	928'	949'	Lenepah	928'
Shale	981'	1054'		981'
Limestone	1054'	1080'	Oswego	1054'
Shale	1114'	1121'		1114'
Limestone	1121'	1135'	Brezzy Hill	1121'
Sand	1522'	1538'		1522'
Chat	1587'	1591'	Mississippi	1587'
Brown Limestone	1602'	1687'		1602'
Shaley Limestone	1763'	1771'	Green & Brown	1763'
Brown Limestone	1771'	1824'		1771'
Dark Limestone	1845'	1870'		1845'
Limestone	1876'	1919'		1876'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date