

**AFFIDAVIT OF COMPLETION FOR State Geological Survey CO-1  
WICHITA, BRANCH**

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Benson Mineral Group, Inc.

API NO. 15-125-24,499

ADDRESS 1726 Champa St., Suite 600  
Denver, CO 80202

COUNTY Montgomery

FIELD Jefferson-Sycamore

\*\*CONTACT PERSON Jim Jameson

PROD. FORMATION Bartlesville

PHONE 303-893-0883

LEASE Erwin

PURCHASER Union Gas System, Inc.

WELL NO. 3-32

ADDRESS P. O. Box 347  
Independence, KS 67301

WELL LOCATION C NE SW SW

990 Ft. from S Line and

990 Ft. from W Line of


the SW 1/4 SEC. 32 TWP. 34S RGE. 16E

DRILLING Downs Drilling Company

CONTRACTOR

ADDRESS 5401 S. Sheridan, Suite 301  
Tulsa, OK 74145

PLUGGING  
CONTRACTOR  
ADDRESS



WELL PLAT

KCC   
KGS   
MISC   
(Office Use)

TOTAL DEPTH 927 PBDT 927

SPUD DATE 12-18-81 DATE COMPLETED 12-21-81

ELEV: GR 739 DF      KB     

DRILLED WITH (CABLE) ROTARY, AIR TOOLS New / (Used) casing.  
CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 5/8	7"	17.0	65	common	9	CaCl
Production	6 1/4	4 1/2"	9.0	865	common	82	2% gel

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			None		
Size	Setting depth	Pecker set at			
None					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Natural	

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

Date of first production <u>SIGW</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Flowing</u>	Gravity
DATE OF PRODUCTION PER 24 HOURS	Oil <u>    </u> Gas <u>55</u> Water <u>%</u>	Gas-oil ratio <u>    </u>
Disposition of gas (vented, used on lease or sold) <u>Sold</u>	Perforations <u>Open hole</u>	

\*\*The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Alluvium Depth 45'

Estimated height of cement behind Surface Pipe 65'

DV USED? No

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Overburden	0	2		
Clay	2	10		
Quick Sand	10	34		
Sand	34	45		
Shale	45	168		
Sandy shale	168	176		
Shale	176	191		
Lime	191	193		
Grn shale	193	195		
Lime	195	196		
Sand	196	198		
Shaley sand	198	205		
Sandy shale	205	227		
Shaley sand	227	238		
Sandy shale	238	251		
Shale	251	268		
Lime	268	280		
Shale	280	282		
Shaley sand	282	289		
Lime	289	293		
Shaley sand	293	296		
Limey sand	296	298		
Sandy shale	298	305		
Shale	305	307		
Sandy shale	307	312		
Shaley sand	312	323		
Sandy shale	323	328		
Shaley sand (water)	328	335		
Sand (oil)	335	353		
Lamanated sand & shale	353	380		
Shale	380	426		
Lime	426	427		
Shale	427	432		
Lime	432	453		
Shale	453	460		
Grn shale	460	468		

SEE ATTACHED

AFFIDAVIT

STATE OF Colorado, COUNTY OF Denver SS, \_\_\_\_\_

James S. Jameson OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,  
DEPOSES THAT HE IS Vice President (FOR)(OF) Benson Mineral Group, Inc.

OPERATOR OF THE Erwin LEASE, AND IS DULY AUTHORIZED TO MAKE  
THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 3-32 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 21st DAY OF December, 1981, AND THAT  
ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) James S. Jameson

SUBSCRIBED AND SWORN BEFORE ME THIS 5th DAY OF February 1982

Wendell M. Markel  
NOTARY PUBLIC

MY COMMISSION EXPIRES: July 25, 1982