

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


7-34-2E

Company- SHAWVER-ARMOUR, INC.,
Farm- Sharpsteen No. 1

SEC. 7 T. 34 R. 2E
NE NE NE

Total Depth. 4050'
Comm. 9-5-58 Comp. 9-21-58
Shot or Treated.
Contractor. Shawver-Armour, Inc. ET AL.
Issued. 11-8-58

County Sumner
KANSAS



CASING:

3 5/8" @ 190' W/160 sks. cem.,

Elevation. 1232' KB.

Production. Dry.

Figures Indicate Bottom of Formations.

soil & sand	15
shale & lime	145
shale & lime	155
Anhydrite & shale	190
shale & Anhydrite	235
Anhydrite & shale	445
shale & lime	870
shale & lime shells	1395
shale & lime	1630
shale & lime Strks.	1810
lime & shale	1904
shale & lime	2245
lime & shale	2510
Stalnaker Sand	2614
sand & shale	2648
shale & lime	2845
shale	2936
sand	2943
sand & sandy shale	3014
sand	3042
shale	3084
Kansas City Lime	3115
lime	3197
lime & shale	3493
shale & lime	3541
Mississippi lime	3557
Mississippi chert & lime	3609
Mississippi lime	3616
lime & chert	3643
lime	3794
lime & shale	3833
shale	3871
Simpson sand	3878
Simpson	3948
Arbuckle Lime	4050
Total Depth.	

Osage	3051
Cherokee	3384
Mississippi	3541
Kimberly	3609
Clinton	3640
Arbuckle	3942

TOPS:

Stalnaker	2512
Layton	2936
Base Layton	3040
Kansas City	3084