

UNION NATIONAL BANK BLDG WICHITA KANSAS

23 34-2E
Sec. 23 T. 34 R. 2E.

Location NW SW SE.

County- Sumner. APR 15 1929

Casing Record
 20" 10" Farm- Warner No. 1
 15 3/8" 3 1/2" Company- Marland Oil Co.
 12 3/8" 65/8" Contr.-
 12 3/8" 53/16" Comm.- 10/24/28. Comp.- 4/3/1929.
 Total Depth 3861'. Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Elevation 1215

Figures Indicate Bottom of Formations.
 Date Issued. 4/13/1929.

Initial Production Dry.

Formation	Depth	Formation	Depth
sft mud Set 20" at 31'	220	hrd sand HFW	1960
shale	340	sft shale	1965
lime	350	Set 10" at 1979'	
shale sft	460	hrd lime	1995
brkn lime sft	510	sft shale	2005
red mud sft	520	shelly lime	2030
hrd lime	530	sft shale	2125
blue mud sft	540	UR 10" to 2100-85'	
hrd lime	552	lime hrd	2135
blue mud sft	560	shale sft	2210
hrd lime	565	sft shale	2325
lime sft	570	lime hrd	2335
blue mud	600	sft shale	2385
lime	620	hrd sand	2395
mud red sft 8 BPH	630	sft shale	2405
brkn lime at 600'	680	hrd sand HFW	2435
shale sft	695	Ran 8 1/4" csg. 2435'	
lime hrd	700	hrd sand	2545
shale sft	720	sft shale	2605
hrd lime	735	8 1/2" UR to 2601'	
red mud sft	800	sft shale	2750
15 3/8" set at 800'		sft shale	2800
lime hrd	830	hrd sand water at 2808	2820
shale sft	835	brkn lime HFW	2860
lime hrd	880	hrd sand	2885
shale sft	890	sand hrd	2890
hrd lime	935	limey sand hrd	2910
sft shale	945	sft shale	2980
lime hrd	970	hrd lime	2990
sft shale	1025	sft shale	2995
hrd lime	1030	lime drk gray hrd	3095
shale sft	1165	white shale sft	3155
hrd sand HFW	1190	hrd lime	3158
blue shale sft	1235	shale sft	3190
Set 12 1/2" 1195'		hrd lime	3290
hrd lime	1240	6 5/8" set 3205'	
blue shale	1270	black shale sft	3420
hrd lime	1280	shale sft	3456
sft shale	1300	hrd sand with sft spots	3478
hrd lime	1330	4 M. Gas.	
sft shale	1370	sandy lime hrd 6 M. Gas	3480
lime hrd	1380	sand hrd	3490
sft shale	1385	sand hrd	3505
hrd lime	1390	chat Show oil	3509
sft shale	1430	sandy lime 3523 WTR	3523
hrd sand 4 BWPH	1435	sandy lime HFW 3547	3547
sft shale	1460	lime hrd very hrd	3720
hrd lime	1470	Set 5 3/16" csg. 3500'	
sft shale	1495	shale	3724
hrd lime	1555	white lime	3730
sft shale	1565	shale & shells	3790
hrd sand HFW	1590	sand hrd	3797
shale sft	1655	sand sft	3818
lime sft 1 BW 1660'	1670	sand hrd 6 BW in 12 hrs	3830
shale sft	1685	hrd sand 3828-3830	3861
hrd lime	1740	1500' wtr in hole at 3861'.	
shale sft	1770		
hrd lime	1800	Total Depth	3861'.
hrd sand	1810		
hrd lime	1840		
black sft mud	1845		
shale sft	1945		