

WELL RECORD

Well No. **011** Farm **Pickering**

Producer **GMA, Inc.**

Location

Sec **28** Twp **34** Rg **70 E**

Elevation

State **Kansas** County **Labette**

Kind (Oil, Gas, Water, Dry Hole) **Oil**

Contractor **ACE-HI EXPLORATION Co.**

Producing formation

Top

Bottom

Shot with

q's

from

to

Packer Set at

Kind

Size

Line

from

to

Perforated from

to

LOG

Strata	Depth	Thick- ness	Strata	Depth
9' Soil & clay	9'			
19 Lime	28			
30 Bl. Shale	30			
3 Lime	33			
73 Sdy shale	106			
10 Shale	125			
6 Sdy. shale	131			
CORE #1				
131' to 142 1/2'				
50 Sdy. shale	148			
5 Lime	153			
36 Sh. & sdy sh.	189			
1 Lime	190			
58 Sh. & sdy sh.	248			
40 Sdy. shale	288			
4 Sand "Brkn"	292			
288 Sh. & sdy. sh	580			
2 Lm. "oil show	582			
CORE #2				
582' to 601'				
1 Sdy. Lm				
bleeding oil	583			
3 Sand/sh/lm	586			
15 Miss lime	601			

Total Depth **601'**

Open Hole

Casing **8 5/8"** at **26.75'**

Casing at

Casing at

Cement

Tubing

Rods

Additional Information

Plugging-- 7 sks cement on bottom
--Mud to 150' Bridge at 150'
with 8 sks ~~mud~~ cement-- Mud
to 65'--Bridge with 3 sks
cement at 65'--Dirt to top
and 2 sks. cement.

Acc#H# plugging number 589

All measurements taken
from ground level.

Date started-- Sept. 18, 1965

Date Completed --Sept. 19, 1965

O. K.

Superintendent