

29-34-21

County Labette  
State Kansas  
Lease Ralph Tullis  
Well # 1

Contractor S.J. Poteet  
Drilling comm. 9/18/52  
Drilling complete 10/24/52  
Driller S.J. Poteet Helper W.C. Johnson

Location -----SW and NW of NW 29-34-21  
Casing 10" -----130 -----8 1/2 -----787 -----6 1/2 -----927

Drillers record of formation.

0-4---- Soil ---10" hole

---

4-19---- Lime

19-75---- Gray shale

75-85---- Sand About 5 gallon water per hour

85-98---- Gray shale

98-100--- Lime shell

100-106--- Gray shale

106-112--- Ardmore lime

112-140--- Gray shale D. Reduced to 8 1/2 at 130 ft.

140-150--- Sand

150-200---- Gray shale

208-250---- Gray shale

250-260--- Shaley sand

260-550--- Gray shale

550-570--- Sand lime

570-635--- Gray lime 1/2 baler of water per hour.

635-674--- Brown lime

674-735--- Gray lime and flint----1 baler of water per hour.

735-745--- Dark gray lime

745-755--- White lime

755-790--- Gray lime and flint----Reduced from 8 1/2 to 6 1/2 at 787

790-845--- Dark gray lime

845-890--- Gray green lime shale streaks.

890-902--- Gray lime

902-908--- Green shale

908-912--- Green lime

912-916--- Gray lime

916-924--- Black shale

924-925--- Brown lime cap

925-927--- Arbuckle lime Fresh water

927----- Arbuckle lime-----Tore down.

Completed as water well

S.J. Poteet

This Well is approximately 30 feet higher  
on surface elevation than the Chetopa Oil  
Field.