

G

Company: Eagle-Picher

Sec. 26 T. 34 R. 23

Farm: A. B. Thomas

No. P-6

Loc. SW SE--center of  
West 40 A.

Comm. December 17, 1938

County: Cherokee

Comp. January 3, 1939

Total Depth: 442

Contractor: George Provine

Water Level: 280

Driller: F. W. Doty

Elev. 882

Helper: Mearl Doty

Formation

	Thickness	Depth
surface clay	25	25
shale	120	145
sand, gray; shale	10	155
shale	33	188
lime, sandy; mundic	2	190
lime, gray	10	200
no cuttings. openings 202-208 lost water	8	208
lime; shale; tiff; boulders	2	210
flint, blue gray	10	220
flint, light gray and gray blue; sand, blue	10	230
flint, light gray; little sand, blue	5	235
flint, gray; lime, dark gray	5	240
flint, gray; little lime, gray	20	260
flint, gray; lime, gray	5	265
flint, gray and blue; lime, gray brown	25	290
flint, blue; lime, brown	15	305
flint, gray	5	310
cotton rock	25	335
flint, gray	5	340
lime, brown, gray, white; flint, gray	10	350
flint, gray; lime, gray brown	5	355
lime, brown and gray; very little flint	5	360
flint, gray; lime, gray and brown	20	380
flint, gray	10	390
flint, gray and brown	5	395
flint, gray and blue; lime, gray	10	405
lime, dark gray; flint, gray blue	5	410
flint, blue, gray, brown; lime, gray brown	10	420
lime, brown and gray; flint, gray blue	20	440
flint, gray brown; lime, pale brown	2	442

Surface water 25'

Lost water 202

More water 208

Water stands 280