

G

Company: Eagle-Picher

Sec. 6 T. 34 R. 24

Farm: O. A. Rhodes

No. 1

Loc. C SW SW

Comm. February 6, 1942

County: Cherokee

Comp. February 19, 1942

Total Depth: 443

Contractor: W. J. Swalley

Water Level: 182

Driller: Lloyd George

Elevation: 898'

	Formation	
	Thickness	Depth
soil	1	1
clay, yellow; sandstone	9	10
soapstone, light gray	45	55
soapstone, dark	10	65
soapstone, light gray	60	125
shale, gray sandy	15	140
shale, dark gray	25	165
shale, dark	25	190
sandstone, shale, dark gray	10	200
shale, dark	15	215
specks of gray lime, shale and mundic	5	220
lime, gray; mundic	15	235
soapstone shells of lime and mundic	5	240
soapstone and mundic	10	250
lime, gray; mundic	15	265
lime, gray; flint, light gray	30	295
lime, gray; flint, gray; selvage	15	310
cotton rock; flint, gray	15	325
some cotton rock; flint, gray, gray and brown speckled	5	330
lime, tan; flint, gray	20	350
flint, gray and light gray	10	360
lime, gray and brown; flint, light gray	5	365
lime, brown; specks of gray flint	5	370
lime, gray and brown	5	375
lime, gray and brown; flint, gray	5	380
flint, gray and light brown; specks of brown lime	5	385
flint, gray and light gray; soapstone cavings	10	395
flint, gray and light gray; trace of lead	5	400
flint, gray and light gray; few specks of lead	5	405
flint, gray and light gray, some gray and brown speckled	10	415
lime, gray; flint, gray and light gray	15	430
lime, gray; flint, gray and pale blue	13	443

water at 25 ft.

some water at 315 ft.

strong water at 385 ft.

85 ft. of 6 $\frac{1}{2}$ casing